

AD-A067 766


LANGAN ENGINEERING ASSOCIATES INC CLIFTON NJ
NATIONAL DAM SAFETY PROGRAM. LAKE MUSCONETCONG DAM(NJ00328). DE--ETC(U)
APR 79 D J LEARY

F/G 13/2
DACW61-78-C-0124
NL

UNCLASSIFIED

1 of 2
AD
A067766





DELAWARE RIVER BASIN
MUSCONETCONG RIVER
MORRIS COUNTY
NEW JERSEY

Q

LAKE MUSCONETCONG

DAM

NJ 00328

DDC
PAPERS
APR 25 1979
C

ADA067766

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

LEVEL II



Approved for public release;
distribution unlimited

DDC FILE COPY.

ORIGINAL CONTAINS COLOR PLATES: ALL DDC
REPRODUCTIONS WILL BE IN BLACK AND WHITE.

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

April, 1979
79 04 20 05

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.

—
THIS IS THE BEST

COPY AVAILABLE.



DEPARTMENT OF THE ARMY
 PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
 CUSTOM HOUSE - 2 D & CHESTNUT STREETS
 PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO
 NAPEN-D

12 APR 1979

Honorable Brendan T. Byrne
 Governor of New Jersey
 Trenton, New Jersey 08621

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Lake Musconetcong Dam in Morris County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Lake Musconetcong Dam, a high hazard potential structure, is judged to be in fair overall condition. However, the spillway is considered inadequate since 72 percent of the Probable Maximum Flood (PMF) would overtop the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.

b. Within six months from the date of approval of this report, engineering studies and analysis should be performed to determine the dam's foundation conditions and structural stability. Any remedial measures found necessary should be initiated within calendar year 1980.

ion	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
tion			
ANNOUNCING			
SPECIFIC			
DISTRIBUTION/AVAILABILITY CODES			
SPECIAL			
			23
			A

NAPEN-D

Honorable Brendan T. Byrne

c. Within six months of the date of approval of this report, the following remedial actions should be completed:

(1) Trashracks should be installed at the gatehouse intake. A means of hoisting the trashrack into and out of its channels should also be provided.

(2) The crack in the joint of the downstream face of the spillway should be repaired.

(3) Inspection and repair, if necessary, of the concrete of the spillway discharge channel at the upstream toe of the dam should be performed when no water is flowing over the spillway.

(4) Spalled and eroded areas on the downstream face of the spillway, the sidewalls, the discharge outlet structure, and the upstream end of the culvert under Route 206 should be repaired.

(5) An evaluation should be made of the ability of the iron picket fence, along Route 206, to stop a fast moving heavy vehicle from accidentally falling into the spillway discharge channel.

(6) Within twelve months, from the date of approval of this report, the depression in the concrete sidewalk along Route 206 should be investigated and repaired.


A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman James J. Courter of the Thirteenth District. Under the provisions of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

NAPEN-D
Brendan T. Byrne

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,


JAMES G. TON
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Copies furnished:
Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N. J. Dept. of Environmental Protection
P. O. Box CN029
Trenton, NJ 08625

John O'Dowd, Acting Chief
Bureau of Flood Plain Management
Division of Water Resources
N. J. Dept. of Environmental Protection
P. O. Box CN029
Trenton, NJ 08625

LAKE MUSCONETCONG DAM (NJ00328)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 7 and 14 December 1978 by Langan Engineering Associates, Inc. under contract to the State of New Jersey. The state, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Lake Musconetcong Dam, a high hazard potential structure, is judged to be in fair overall condition. However, the spillway is considered inadequate since 72 percent of the Probable Maximum Flood (PMF) would overtop the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.

b. Within six months from the date of approval of this report, engineering studies and analysis should be performed to determine the dam's foundation conditions and structural stability. Any remedial measures found necessary should be initiated within calendar year 1980.

c. Within six months of the date of approval of this report, the following remedial actions should be completed:

(1) Trashracks should be installed at the gatehouse intake. A means of hoisting the trashrack into and out of its channels should also be provided.

(2) The crack in the joint of the downstream face of the spillway should be repaired.

(3) Inspection and repair, if necessary, of the concrete of the spillway discharge channel at the upstream toe of the dam should be performed when no water is flowing over the spillway.

(4) Spalled and eroded areas on the downstream face of the spillway, the sidewalls, the discharge outlet structure, and the upstream end of the culvert under Route 206 should be repaired.

(5) An evaluation should be made of the ability of the iron picket fence, along Route 206, to stop a fast moving heavy vehicle from accidentally falling into the spillway discharge channel.

(6) Within twelve months, from the date of approval of this report, the depression in the concrete sidewalk along Route 206 should be investigated and repaired.

APPROVED:

James G. Ton

JAMES G. TON
Colonel, Corps of Engineers
for District Engineer

DATE:

12 April 1979

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**

NAME OF DAM:	LAKE MUSCONETCONG DAM
ID NUMBER:	FED ID No NJ00328
STATE LOCATED:	NEW JERSEY
COUNTY LOCATED:	MORRIS
STREAM:	MUSCONETCONG RIVER
RIVER BASIN:	DELAWARE
DATE OF INSPECTION:	DECEMBER 1978


ASSESSMENT OF GENERAL CONDITIONS

Lake Musconetcong is 52 years old and in fair overall condition. There is spalling, deterioration, and cracking of concrete at different locations on the dam, spillway, and outlet works that should be repaired.

The spillway capacity as determined by CE Screening criteria is inadequate. We estimate the dam can adequately pass 71% of the PMF. We recommend trashracks be installed at the gatehouse intake. A means of hoisting the trashrack into and out of its channels should also be provided. This should be done soon. The crack in the joint of the downstream face of the spillway should be repaired. This should be done soon. An inspection of the concrete of the spillway discharge channel at the upstream toe of the dam should be performed when no water is flowing over the spillway. This should be done soon. The engineering properties of the dam foundation material should be investigated by means of borings and tests, and stability analysis made using present day methods to confirm our assumptions concerning the structural

stability of the dam and appurtenances under different stress conditions. This should be done soon. Spalled and eroded areas on the downstream face of the spillway, the sidewalls, the discharge outlet structure, and the upstream end of the culvert under Route 206 should be repaired. This should be done in the near future. The iron picket fence along Route 206 should be cleaned and painted and an evaluation made of its ability to stop a fast moving heavy vehicle from accidentally falling into the spillway discharge channel. This should be done in the near future. The depression of the concrete sidewalk along Route 206 should be investigated and repaired. This should be done in the future.

The spillway capacity as determined by CE Screening criteria is inadequate. The actual capacity of the spillway and the SDF should be determined using more precise and sophisticated methods and procedures. The need for and type of mitigating measures should be determined. Around the clock surveillance during periods of unusually heavy precipitation should be provided, and a warning system established. This should be done in the near future.



Dennis J. Leary, P.E.



OVERVIEW
LAKE MUSCONETCONG DAM
1 DECEMBER 1978

**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**

NAME OF DAM:	LAKE MUSCONETCONG DAM
ID NUMBER:	FED ID No NJ00328
STATE LOCATED:	NEW JERSEY
COUNTY LOCATED:	MORRIS
STREAM:	MUSCONETCONG RIVER
RIVER BASIN:	DELAWARE
DATE OF INSPECTION:	DECEMBER 1978



LANGAN ENGINEERING ASSOCIATES, INC.

Consulting Civil Engineers

**990 CLIFTON AVENUE
CLIFTON, NEW JERSEY**

201-472-9366

CONTENTS
NATIONAL DAM SAFETY REPORT
LAKE MUSCONETCONG DAM FED ID No. NJ00328

	<u>PAGE</u>
PREFACE	
SECTION 1 PROJECT INFORMATION	
1.1 <u>General</u>	1
1.2 <u>Project Description</u>	1
1.3 <u>Pertinent Data</u>	2
SECTION 2 ENGINEERING DATA	
2.1 <u>Introduction</u>	4
2.2 <u>Regional Geology</u>	4
SECTION 3 VISUAL INSPECTION	5
SECTION 4 OPERATIONAL PROCEDURES	6
SECTION 5 HYDRAULIC/HYDROLOGIC	6
SECTION 6 STRUCTURAL STABILITY	7
SECTION 7 ASSESSMENT, RECOMMENDATIONS/ REMEDIAL MEASURES	
7.1 <u>Assessment</u>	7
7.2 <u>Recommendations/Remedial Measures</u>	8
FIGURES	
1. Regional Vicinity Map	
2. Essential Project Features	
3. Regional Geologic Features	
APPENDICES	
1. Hydrologic Data	
2. Check List, Visual Inspection	
3. Photographs	
4. Hydrologic Computations	
5. References	

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

SECTION I PROJECT INFORMATION

1.1 General

Authority to perform the Phase I Safety Inspection of Lake Musconetcong Dam was received from the State of New Jersey, Department of Environmental Protection, Division of Water Resources by letter dated 20 November 1978. This Authority was given pursuant to the National Dam Inspection Act, Public Law 92-367 and by agreement between the State and the US Army Corps of Engineers District, Philadelphia, Penn.

The purpose of the Phase I Investigation is to develop an assessment of the general conditions with respect to safety of Lake Musconetcong Dam and appurtenances based upon available data and visual inspection, and, determine any need for emergency measures and conclude if additional studies, investigations and analyses are necessary and warranted. The assessment is made using screening criteria established in Recommended Guidelines for Safety Inspection of Dams prepared by the Department of Army, Office of the Chief of Engineers. It is not the purpose of the inspection report to imply that a dam meeting or failing to meet the screening criteria, is per se, certainly adequate or inadequate.

1.2 Project Description

Lake Musconetcong Dam is a 52 year old, 14-ft high, 237-ft long highway embankment dam (Route 206) with a concrete upstream retaining wall and an upstream over-fall type spillway. The downstream slope of the dam on the west side of Route 206 is about 1½ Hor. to 1 Vert. or flatter. The concrete crest of the spillway has been raised one foot by means of timber planks bolted to the top. There is a longitudinal spillway channel parallel to and upstream of Route 206. The retaining wall forms the downstream side of the spillway channel. There is a gatehouse with four 3-ft-wide by 5-ft-high sluice gates and a 36-inch discharge pipe at the right abutment. The spillway is a concrete weir 203 ft long and discharge from the spillway channel is by way of a culvert under Route 206 into the Musconetcong River. The four sluice gates discharge directly into the spillway discharge channel and into the culvert. Discharge from the pipe crosses Route 206 and into the Morris Canal.

The dam is located in the Borough of Netcong on the Musconetcong River Morris County, New Jersey. It is at the southwest end of Lake Musconetcong at north latitude 40° 54' and west longitude 74° 42.3. A regional vicinity map is given in Fig 1 and essential features of the dam and appurtenances are given in Fig 2.

Lake Musconetcong Dam is classified as being "Intermediate" on the basis of its maximum reservoir storage volume of 3370 ac-ft which is more than 1,000-acre feet, but less than 50,000-acre feet. It is classified as "Small" on the basis of its total height of 14 ft, which is less than 40 feet. The overall size classification is the larger of these two determinations, and accordingly the dam is classified as "Intermediate" in size.

In the National Inventory of Dams, Lake Musconetcong Dam has been classified as having "High Hazard Potential" on the basis that failure of the dam would cause excessive property damage to residences downstream, and could potentially cause more than a few deaths. Visual inspection of the downstream area shows that breach of the dam would cause damage to residences and be hazardous to people utilizing Route 206. Accordingly, it is proposed not to change the Hazard Classification Potential.

The dam is owned by the State of New Jersey Department of Environmental Protection, Div. of Parks and Forestry, P.O. Box 1420 Trenton, N.J. 08625.

The purpose of the dam is flood control and recreation. The dam was designed by Corneleus C. Vermeule, Consulting and Direction Engineer for the Morris Canal and Banking Company. It was constructed by the John W. Heller Company in 1927. There is essentially no information available on the design and construction history of the dam.

1.3 Pertinent Data

- | | | |
|----|--|---|
| a. | The drainage area is: | 30.3 sq mi |
| | The area of the Lake is: | 307 Acres |
| b. | Discharge at Dam Site | |
| | Maximum known flood at dam site: | October 1903; peak flow reported to be 2331 cfs at Lake Hopatcong |
| | Ungated spillway capacity at maximum pool elevation: | 3460 cfs (controlled by culvert under roadway) |
| | Total spillway capacity at maximum pool elevation: | 3460 cfs (controlled by culvert under roadway) |
| c. | Elevation (ft above MSL) | |
| | Top dam: | Approx. El. 863.5 (low point at two ends) |

	Spillway crest:	El. 859.75
	Streambed at centerline of dam:	Approx. El. 849.
	Maximum tailwater:	Approx. El. 851. at time of inspection
d.	Reservoir	
	Length of maximum pool:	Approx. 14,000 feet
	Length of normal pool:	Approx. 13,900 feet
e.	Storage (acre-feet)	
	Top of dam:	Approx. 3370 AF
	Spillway crest:	Approx. 2200 AF
f.	Reservoir Surface (acres)	
	Top Dam:	Approx. 318 Acres
	Spillway crest:	307 Acres
g.	Dam	
	Type:	Highway embankment with U/S concrete face
	Length:	237 feet
	Height:	14 feet
	Top width:	63 Feet (roadway embankment width)
	Zoning:	None observed
	Impervious Core:	None observed
	Cutoff:	None observed
	Grout curtain:	None observed
h.	Spillway	
	Type:	Over-fall
	Length of weir:	203 feet

Crest elevation:	El. 859.75
U/S Channel:	None observed
D/S Channel:	Longitudinal concrete channel
i. Regulating outlets	Four 3 ft x 5 ft vertical lift sluice gates and a control valve on a pipe leading from the right of the gatehouse. Discharge is controlled from gatehouse at right abutment.

SECTION 2 ENGINEERING DATA

2.1 Introduction

In 1931 consideration was given to raising the crest of the spillway by 2.0 ft. This led to the development of technical letters by the Engineer C.C. Vermeule concerning the hydrologic aspects of Lake Musconetcong and the spillway. These letters are given in Appendix 1. The spillway was not raised as originally proposed. However, the crest was raised 1 ft by means of timber planks bolted to the crest of the existing concrete weir. These planks have been maintained and were in place at the time of our inspection.

No essential engineering information is available concerning the design and construction of the dam. Consequently, an evaluation cannot be made.

Operation of the outlet works consists of maintaining a flow in the pipe leading to the Morris Canal. This water is used by the Stan Hope Fire Department for fire protection. During the winter a flow of water is maintained over the spillway to prevent freezing at the spillway crest and the left sluice gate is kept open slightly to prevent build up of ice and permit measurement of water levels.

2.2 Regional Geology

Lake Musconetcong Dam is located in the New Jersey Highlands physiographic province. The New Jersey Highlands extend across the State in a northeast/southwest direction from the border of New York to the Delaware River and includes the northwest portions of Hunterdon, Passaic, and Morris Counties and the southeastern parts of Warren and Sussex Counties. The province is part of the New England Physiographic Province and lies between the Appalachian Ridge and Valley Province to the northwest and the Piedmont Province to the southeast, See Fig 3.

The Highlands are characterized by rounded and flat-topped northeast/southwest ridges and mountains up to 1,400 ft high separated by narrow valleys. The orientation of the valleys are usually, but not always controlled by the underlying geologic structure.

Bedrock of the region is predominantly Precambrian gneisses, schists, and metasediments. Some sedimentary strata, typically sandstones, shales and conglomerate have been infolded and faulted into the valley bottoms.

The regional geologic structure reflects the very old age of bedrock. A number of regional faults cross the area in a northeast southwest direction, including the Ramapo Fault; the more than 30 mile long fault/scarp forms the eastern border of the province. Faults control many of the river valley orientations. The relatively uniform slope of the mountain elevations, from northwest to southeast, is a direct result of the faulting. The entire area is part of the now dissected Schooley Peneplain.

The Pleistocene Age Wisconsin glacier covered all of the dam site area.

The glacier stripped most of the existing overburden and weathered rock and uncovered the numerous hard bedrock knobs and ridges seen throughout the province. Most of the side-slopes in the area are covered with heavy boulder tills (ground moraine), whereas glacial outwash and recent alluvium cover the valleys.

SECTION 3 VISUAL INSPECTION

Approximately one inch of water was flowing over the spillway crest at the time of our inspection which limited the extent of our observations. However, based on those parts of the dam and appurtenances we could observe it is our opinion the dam is in generally fair condition.

Several construction joints perpendicular to the axis of the spillway crest appeared open. Wooden flashboards approximately one foot high are attached to the spillway crest. Water was not flowing uniformly over the flashboards. The mid-portion of the spillway had less head flowing over boards.

The gatehouse contains five Coffin gate valve operators. The valves are well maintained and easily operated by one man.

The left concrete spillway sidewall has deteriorated upstream and the soil has eroded to a depth of about 2 ft behind the sidewall.

Spillway discharge goes under Route 206 through a concrete culvert into the Musconetcong River. To the right and parallel to the river is a portion of the old Morris Canal that feeds into the river further downstream.

The downstream face of the spillway has small spalled areas and vertical cracks at construction joints. Spalling and deterioration of the concrete has occurred at the discharge outlets of the gatehouse.

Deterioration of the concrete has occurred at the entrance to the culvert which crosses beneath Route 206. A small amount of debris has collected in the spillway discharge channel. The riprap at the left end of the spillway and the right side of the gatehouse is missing. Erosion and deterioration of concrete has occurred at the right downstream sidewall of the culvert under Route 206 and erosion has occurred at the left downstream sidewall.

A section of the sidewalk above the dam has depressed about 2 inches. The iron fence along Route 206 has rusted and appears to have at one time stopped a vehicle from falling into the discharge channel.

The earth slopes surrounding the lake are relatively flat and no adverse conditions were observed. Our Visual Inspection Check List is given in Appendix 2 and Photographs are given in Appendix 3.

SECTION 4 OPERATIONAL PROCEDURES

Operation and maintenance of the dam is the responsibility of the N.J.D.E.P. Division of Parks and Forestry. There are four 3 ft by 5 ft vertical lift sluice gates and a control valve on a 36-in-dia pipe. The operator stands are manufactured by Coffin of Boston. They are well maintained and in good condition. They can be operated by one man. The 36-in-dia pipe provides a constant flow of water to the Morris Canal which is used by the Stan Hope Fire Department for fire protection. The sluice gates are seldom opened except in the winter when the left gate is maintained open slightly to prevent ice forming and permits water level measurements.

SECTION 5 HYDRAULIC/HYDROLOGIC

No information is available concerning original design data for Lake Musconetcong Dam. The results of studies made in 1931 subsequent to its construction have been given in Appendix 1.

The hydraulic/hydrologic evaluation is based on a Spillway Design Flood (SDF) equal to the full Probable Maximum Flood (PMF) chosen in accordance with the evaluation guidelines for dams classified as high hazard and Intermediate in size. Hydrologic design data for this dam is not available. The PMF has been determined by developing a synthetic hydrograph based on the maximum probable precipitation of 22.4 inches (200 square mile - 24 hour). Hydrologic computations are presented in Appendix 4. The PMF peak inflow determined for the subject watershed is 6140 cfs.

The capacity of the spillway is 3460 cfs which is less than SDF.

Flood routing for the PMF (with the gates closed) indicates the dam will overtop by 1.8 ft. We estimate with gates closed the dam can adequately pass 71% of the PMF.

The downstream potential damage center is a well traveled highway (Route 206) across the crest of the dam and nearby residential buildings, which are located downstream of the dam. Based on our visual inspection of the immediately downstream topography and knowledge of the dam it is our opinion that dam failure resulting from overtopping would cause excessive property damage and could potentially cause more than a few deaths.

Drawdown of lake below spillway crest has been evaluated considering the four 3 ft x 5 ft sluice gates and the 36-in-dia discharge pipe function properly and are utilized for this purpose. Our calculations indicate the lake level could be lowered 5 ft in approximately 1 day and 9 ft in about 5 days.

SECTION 6 STRUCTURAL STABILITY

There is no available information concerning the dam foundation material. However, it is our opinion based primarily upon our visual observations, and evaluation of the type and conditions of the dam, that it is stable under static loading and is likely to have conventional safety margins.

Lake Musconetcong Dam is located in Seismic Zone 1 of the Seismic Zone Map of Contiguous States. In its present condition the degree of structural stability is assumed to be adequate with respect to both static and seismic loadings.

SECTION 7 ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES


7.1 Assessment

Lake Musconetcong is 52 years old and in fair overall condition. There is spalling, deterioration, and cracking of concrete at different locations on the dam, spillway and outlet works that should be repaired. The spillway capacity as determined by CE Screening criteria is inadequate. We estimate the dam can adequately pass 71% of the PMF.

7.2 Recommendations/Remedial Measures

We recommend the following remedial measures:


1. Trashracks should be installed at the gatehouse intake. A means of hoisting the trashrack into and out of its channels should also be provided. This should be done soon.
2. The crack in the joint of the downstream face of the spillway should be repaired. This should be done soon.
3. An inspection of the concrete of the spillway discharge channel at the upstream toe of the dam should be performed when no water is flowing over the spillway. This should be done soon.
4. The engineering properties of the dam foundation material should be investigated by means of borings and tests, and stability analysis made using present day methods to confirm our assumptions concerning the structural stability of the dam and appurtenances under different stress conditions. This should be done soon.
5. Spalled and eroded areas on the downstream face of the spillway, the sidewalls, the discharge outlet structure, and the upstream end of the culvert under Route 206 should be repaired. This should be done in the near future.
6. The iron picket fence along Route 206 should be cleaned and painted and an evaluation made of its ability to stop a fast moving heavy vehicle from accidentally falling into the spillway discharge channel. This should be done in the near future.
7. The depression of the concrete sidewalk along Route 206 should be investigated and repaired. This should be done in the future.
8. The spillway capacity as determined by CE Screening criteria is inadequate. The actual capacity of the SDF and the spillway should be determined using more precise and sophisticated methods and procedures. The need for and type of mitigating measures should be determined. Around the clock surveillance during periods of unusually heavy precipitation should be provided, and a warning system established. This should be done in the near future.




1 in = 5.2 mi

REGIONAL VICINITY MAP
LAKE MUSCONETCONG DAM

Fig. 1



SECTION A-A
SCALE: 1" = 6'



85 (833.30)

* 84 (834.78)


* 83 (839.16)

* 82 (844.14)

88 x 8


* 86 (841.03)

* 87



CONC. WIND

E



* 83 (839.16)

* 82 (844.14)

88 * 843.49

* 841.57

EL. 853.02

* 86 (841.03)

* 87 (852.41)

* 88 (854.78)

* 89 (854.92)

* 51 (857.61)

* 47 (869.96)

* 43 (865.76)

* 45 (865.84)

* 42 (865.64)

* 26 (864.70)

* 40 (865.48)

* 40 (865.61)

* 39

CONC. WINGWALL

CONC. WINGWALL

EROSION

EROSION

BELL STREET

MORRIS


ASPHALT PATH

CANAL


DIRT ROAD

206


48" R.C.P.



SECTION B-B
SCALE: 1" = 6'



SECTION C-C
SCALE: 1" = 6'



SECTION D-D
N.T.S.

CONC. WINGWALL
EROSION

UNITED
METHODIST
CHURCH

20 (861.98)

ROUTE

SIDEWALK

DEPRESSION

EXP J+3

(852.5)

18 (863.1)

19 (864.10)

SPILLWAY CHAMBER

(856.23)


DETERIORATED CONCRETE


15 (862.20)

RIP-RAP MISSING

14 (860.26)

16 (863.40)






LAKE
MUSCONETCONG
EL. 860.16

PLAN
SCALE: 1" = 30'

NOTE:
THE ELEVATIONS SHOWN WERE OBTAINED FROM SURVEY DATA. THEY ARE APPROXIMATE. THE BENCHMARK WAS SET BY CANAL & BANKING CO. DOVER N.J. OFF SURFACE AND WATER LEVEL ARE INDICATED.

DATE	DESCRIPTION	NO.
REVISIONS		




PROJECT
 PHASE I
 INSPECTION OF EVALUATION
 NEW JERSEY DAMS

DRAWING TITLE
 LAKE MUSCONETCONG DAM
 JANUARY 1979
 FED. I.D. NO. NJ 00328

JOB NO. J-783B	FIG 2
DATE 26 JAN. 1979	
SCALE AS NOTED	
DRN. BY R.Z.	
CHKD. BY D.J.L.	OF SHEETS

ELEVATIONS SHOWN WERE OBTAINED USING A SURVEYORS TRANSIT AND LEVEL.
 ARE APPROXIMATE. THE BENCHMARK ELEVATION OF 864.0 ON THE NORTH
 THE SPILLWAY CHAMBER WAS USED AS INDICATED ON DWGS. OF THE MORRIS
 & BANKING CO. DOVER N.J. OFFICE, JULY 1, 1925 INFORMATION SHOWN BELOW GROUND
 AND WATER LEVEL ARE INFERRED ON THE BASIS OF SAID DWGS.



Schematic Cross-section of
Ridge & Valley
Physiographic Province
(After Wolfe, 1977)

REGIONAL GEOLOGIC FEATURES

Fig. 3

APPENDIX 1

HYDROLOGIC DATA

LAKE MUSCONETCONG DAM

RECEIVED

JUN 1 - 1931

Cornelius C. Vermeule

CONSULTING ENGINEER

38 PARK ROW

NEW YORK

May 29th, 1931.

Mr. Howard A. Britchlow, Chief,
Division of Applications,
State Water Policy Commission,
25 West State Street,
Trenton, N. J.

Dear Mr. Britchlow:

Mr. Sherman, of the Newark Office of your Commission, has suggested that I get in touch with you regarding the spillway capacity at Lake Musconetong after the proposed increased height of 2 ft.

You will note, that the spillway will take care of 1.0 cu.ft. per second per square mile of catchment, either with the gates open or gates closed. I do not believe that the discharge will ever reach this figure. For one hundred years floods at this point were handled through a small gate and through the canal lock. As you know, no spillway existed until 1926.

Due to the pressure of work at this office, it will be impossible for me to go to Trenton within the next week. I am therefore enclosing a memorandum concerning the spillway discharge at this point. I have also sent a copy to Mr. Sherman. I shall be very glad to give you any further information which you may require.

Very truly yours,

Cornelius C. Vermeule, Jr.
Cornelius C. Vermeule, Jr.

Enclosure.

Memorandum Concerning Spillway at Lake

Missconetcong.

This has been computed according to the requirements of the Water Policy Commission, which are stated to be 100 cu.ft. per second per square mile of catchment, which for the 30.3 square miles would call for 3,030 cu.ft. per second. The spillway is 203 ft. long. Co-efficient has been taken at 3.33 in the formula - $Q = 3.33 \times$ the square root of the cube of H.

With the gates closed, the above discharge would call for a height on the spillway of 2.72 ft. and with the gates open 2.15 ft.

There are four sluice gates, each 3 x 5 ft. The elevation of the raised spillway is 861.0, and at the center of the gates 852.5. With 0.5 ft. depth on the spillway, the head on the gates is 9 ft. With $C = 0.62$, the discharge of the four gates is estimated at 896.5 cu.ft. per second.

With the gates open therefore, the height on the spillway required for the above maximum discharge will be as before stated, 2.15 ft.

The net head on the spillway under flood conditions will be as follows:

With the sluice gates closed and $Q = 3,030$ cu.ft. per second, the water will rise in the channel below the spillway and at the gate house to elevation 860.3. At the far end of the spillway the height in the channel will be 862.6.

The water on the spillway will be 863.72. The net head or difference in water level above and below the spillway will be at the gate house 3.42 ft. and at the far end of the spillway 0.92 ft.

With the sluice gates open, the discharge over the spillway will be 2,133.8 cu.ft. per second. The elevation of the water below the spillway at the gate house will be 859.45, and at the far end of the spillway 861.95. The net head on the dam under these conditions will be at the gate house 3.7 ft., and at the far end of the spillway 1.2 ft.

It should be noted from the above figure that the maximum pressure on the dam will occur when the lake is just level with the spillway.

Although the spillway will amply care for the above amount of water, it is far beyond what can ever occur. The discharge from Lake Hopatsong was carefully estimated when the dam was built, and it was found with an inflow to the lake of 115 cu.ft. per second per square mile, owing to the absorption of water by the lake in reaching a given height on the spillway, the discharge over the spillway could not exceed 1260 cu.ft. per second. This maximum would occur at least twelve hours later than the maximum from the lower catchment of 4.9 square miles, and it is estimated from these figures that the maximum discharge over the dam at Lake Masconetsong cannot actually exceed 1400 cu.ft. per second. This will cause a rise of 1.04 ft. on the spillway with the gates closed, or 1.53 ft. with the gates open.

The old canal dam at Saxton Falls stood for nearly one hundred years and could never have remained there had the discharge at that point exceeded 60 cu. ft. per second per square mile.

Cornelius C. Vermeule

CONSULTING ENGINEER

38 PARK ROW

NEW YORK

June 4th, 1931.

Mr. Howard T. Critchlow,
Division Engineer,
State Water Policy Commission,
28 West State Street,
Trenton, N. J.

Dear Mr. Critchlow:

In replying to your favor of the 2nd inst., the spillway was computed on an average co-efficient of 3.33 after we had found that the co-efficient was so close to that that we could use the tables based on the Francis formula. However, I will give you the conditions more in detail as follows:

The water elevations below the spillway are, at the gate house 860.3, at the middle point of spillway 861.07, and at the south end 862.8. The first half of the spillway from the gate house is practically a free discharge, for the reason that the above elevations are not to stillwater as required in the submerged weir formula, but are taken where the velocity is very high, it being impossible to get the figures for still-water. Consequently for the first 101.5 ft. the co-efficient is taken at 3.435. This is from experiments, Series 4 of the Cornell experiments, page 25, U.S. & I. paper 10, 200.

For the remainder of the spillway I have used Vermeule's formula for drowned weirs, see Transactions, American Society C.E., May 1928, page 139. In this paper he gives certain corrections for the head called "a", and after this correction is made, the discharge is computed as if in free air.

The following are the values of H and h, H being the head throughout and h varying.

H = 2.72 at middle point, h = 0.07 at 50.75 ft. south.

Under water
1/2 * 200
p. 134

-2-

At south end $h = 1.80$.

From the above, the value of q for 1 ft. of spillway is worked out as follows:

Middle of spillway, $q = 15.61$ ✓
 At 50.75 ft. south of middle, $q = 14.25$ ✓
 At south end of spillway, $q = 11.36$ ✓

From the above we obtain the following discharges over several sections of the spillway.

First: half from gate house:
 $q = 15.61 \times 101.5 = 1,584$ c.f.s. ✓

For next quarter of spillway:
 $q = 14.93 \times 50.75 = 758$ c.f.s. ✓

For the south quarter of spillway:
 $q = 12.805 \times 50.75 = 650$ c.f.s. ✓

Total discharge 2,992 c.f.s. ✓

This corresponds to a co-efficient of 3.29. However, it does not take into account the fact already stated, that h is not taken to stillwater, and that unquestionably the high velocity below the spillway will increase it. For this reason I consider it conservative to use 3.33 throughout. However, if the above 3.29 is used, the difference in head is trifling.

Taking up next the question you raised as to the discharge from Lake Hopatsong, I did consider present day conditions. This was thoroughly worked out, as I previously stated, when the spillway and gates at Lake Hopatsong were designed. There are four gates there, measuring 3 ft. x 5 ft., and with the water level with the spillway, the head on the center of the gate is 3.5 ft. With a co-efficient of 0.62, this gives a discharge of 129.7 c.f.s. for each gate, or 518 c.f.s. for four gates. The maximum conditions were found to be with all gates open and 1 ft. on the spillway, giving a total discharge as previously stated, of 1260 c.f.s., the spillway being 100 ft. long.

The lake contains 2,445 acres and the total

Mr. Howard T. Britenlow

June 4th, 1931.

-2-

statement indicating the lake is 25.4 sq. miles. He made several computations but I think a single one will show the impossibility of the maximum flow ever reaching above 1260 c.f.s. The inflow is based on the Pequannock in October, 1903, and at that point it began with no discharge. After thirty-three hours it reached 6,000 c.f.s. and at the end of sixty-six hours it had fallen to 1800 c.f.s. Considering the retarding influence of the lake, we may use these figures and taking forty per cent of the above for Lake Hopatcong, which gives an inflow at the end of thirty-three hours of 2400 c.f.s., and at the end of sixty-six hours of 720 c.f.s. At these rates the total volume of inflow would be as follows:

First 33 hours	142,560,000 cu. ft.
Next 33 hours	<u>135,323,000 " "</u>
Total for 66 hours	327,883,000 cu. ft.

If we assume that the gates were open at the beginning of the flood, which would be the condition producing a maximum, we should have the following outflow during the first thirty-three hours, the rise on the spillway being 6 inches.

Through the gates	109,153,440 cu. ft.
Stored in Lake 6 inches	33,203,340 " "
Discharge over spillway	<u>7,009,200 " "</u>
Total Discharge	169,371,180 cu. ft.

For the next thirty-three hours the discharge would continue at the same rate through the gates, but the lake would rise 6 inches further so that the discharge over the spillway would be due to a head of 1 ft. This would dispose of the remainder of the flood as follows:

Discharge through gates	109,153,440 cu. ft.
Stored in Lake 6 inches	33,203,340 " "
Discharge over spillway	<u>26,730,000 " "</u>
	169,191,980 cu. ft.

During the sixty-six hours therefore, the inflow would be 327,883,000 cu. ft. and the offset 338,563,160 cu. ft. The

Mr. Howard P. Britton

June 4th, 1931.

-4-

difference is unimportant I have not recomputed it to make the balance exact.

For the above flood therefore, the maximum discharge occurring at the end of sixty-six hours would be:

Through the gates	916 c.f.s.
Over spillway	<u>342 c.f.s.</u>

Total 1260 c.f.s.

The only use made of the Canal data was in computing the volume of the flood, made up of the amount discharged through the gates plus a very large accumulation in the lake due to the time it was drawn down. These calculations fully demonstrate that there had been no flood at Lake Hopatcong so severe as the one on the Pequannock, upon which we have based the above estimate. The rainfall at Lake Hopatcong is materially less than along the Pequannock.

Perhaps the following presentation will demonstrate more absolutely the impossibility of a discharge from Lake Hopatcong reaching 100 second feet per square mile, or 2540 second feet.

First let us assume that the gates are open, discharging 916.6 second feet. It would then be necessary that the discharge over the spillway should reach 1621.2 second feet to give the above maximum. The spillway is 100 ft. long and to reach this discharge H must equal 2.87 on the spillway. This would require that the lake should fill up 2.87 ft. in the sixty-six hours, and this would absorb 305,416,300 cu.ft.

The discharge over the spillway during 66 hrs. at 916.6 c.f.s. would -	193,881,600 " "
The discharge through the gates for the same period would amount to	<u>218,306,300 " "</u>
This would give a total for 66 hrs. of	717,605,230 cu.ft.

This is of course against the actual inflow as computed before 327,888,000 cu.ft.

It will be seen to have been impossible for the lake to ever rise to a height that would give 2.87 ft. on the spillway.

Mr. Howard T. Britchlow

June 4th, 1931.

-5-

Next let us assume that the gates remained closed. Then in order to reach a discharge of 2540 second feet over the spillway we must have a height above the spillway of 3.87 ft., the lake being filled up to a corresponding height. We should therefore have for the sixty-six hours the following:

3.87 ft. on the lake	411,833,790 cu. ft.
Discharge over spillway, at hrs. @ 1270 second ft.	<u>301,752,000. " "</u>
Total	713,585,790 cu. ft.

This is again considerably more than double the actual amount of the run-off based upon the Pequannock record of 1903.

Concerning the discharge at Saxton Falls in 1903, a careful survey of conditions there as they were before we rebuilt the dam, shows that the water rose on the dam to elevation 95.3. This gave the following spillway conditions.

L = 111.2	
H = 4.4	
Discharge	3,410.5
L = 34.	
H = 2.0	
Discharge	320.3
L = 20.	
H = 1.7	
Discharge	<u>147.6</u>

Total Spillway Discharge 3,878.4

In addition the gate measured 5 ft. x 12.0 ft., or 60.0 sq. ft. with an effective seal of 4 ft. after allowance for back-water. This gives a gate discharge of 976.2.

Total Discharge 4,854.6

At this time there was a steady discharge through the gates at Lake Hopatcong of 240 second feet, which deducted from the above, gives 4309.6 second ft. discharge from the lower 42.6 square miles of catchment, which comes to 101.1 second feet per square mile.

Mr. Howard T. Critenlow

June 4th, 1931.

-6-

This is given to show that whereas 100 second feet per square mile applies to the free catchment, it does not apply to the whole catchment including Lake Hopatcong. You will observe that if 4,854.6 second feet at Saxton Falls is spread over the whole 68 square miles of catchment at that point, it comes to 71.4 second feet per square mile. As previously stated, our experience at Saxton Falls has demonstrated fully that if there had been a discharge there at the rate of 100 second feet per square mile, or 6800 second ft., it would have torn out the abutments of the dam and the canal bank below the dam, due to the rush of water through the lock over the top of the lock, gates and the walls.

Hoping that I have made the above clear, I am

Very truly yours,


Cornelius C. Vermeule, Jr.

107 D.

0

APPENDIX 2

CHECK LIST
VISUAL INSPECTION

LAKE MUSCONETCONG DAM

0

CHECK LIST
VISUAL INSPECTION

Phase I

NAME DAM Lake Musconetcong COUNTY Morris STATE New Jersey COORDINATORS N.J. DEP

DATE(S) INSPECTION See Below WEATHER Overcast TEMPERATURE 45° F

POOL ELEVATION AT TIME OF INSPECTION El. 860.16 M.S.L. TAILWATER AT TIME OF INSPECTION El. 851+ M.S.L.

INSPECTION PERSONNEL:

J. Richards	12/7/78	P. Yu	12/14/78
D. Leary	12/7/78	J. Gurkovich	12/14/78
J. Rizzo	12/14/78		

James Richards RECORDER

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
<p>CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)</p>	<p>Dead branches, wood, bottles, paper, large chunk (2 ft x 3 ft x 1.5 ft) of styrofoam. A rock spillway 600' downstream.</p>	<p>Debris, etc. should be removed.</p>
<p>SLOPES</p>	<p>Varies from vertical stone wall to earth slopes of 1:1 to 1(V) to 3(H). Slopes appear satisfactory.</p>	
<p>APPROXIMATE NO. OF HOMES AND POPULATION</p>	<p>Church, church school, & in excess of 20 homes located downstream. Excess of 200 people.</p>	<p>Warning alarm system & emergency gate should be installed.</p>

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SEE PAGE ON LEAKAGE	None observed	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS (Direction: looking d/s)	At left end of spillway, erosion of over 2 ft in depth and width of 15 ft and length of 25 ft.	Eroded area should be suitably repaired.
DRAINS		
WATER PASSAGES	Generally clear, a few pieces of debris. 150 gpm est coming out of left sluice gate.	Debris should be removed.
FOUNDATION	Not observable.	

**CONCRETE/MASONRY
(SPILLWAY AREA)**

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
<p>SURFACE CRACKS CONCRETE SURFACES (Direction: looking d/s)</p>	<p>Left end of spillway concrete surface cracked over majority of area and spalled to depth of 6 inches. Right end of spillway concrete spalled to depth of 4 inches.</p>	<p>Cracked and spalled concrete should be repaired.</p>
<p>STRUCTURAL CRACKING</p>	<p>Water flowing over spillway at time of investigation. None observed.</p>	
<p>VERTICAL AND HORIZONTAL ALIGNMENT</p>	<p>Vertical alignment of flash boards appears off by 2 inches, water flowing 2 inches higher on left & right of center portion of spillway.</p>	
<p>MONOLITH JOINTS</p>	<p>Appear satisfactory.</p>	
<p>CONSTRUCTION JOINTS</p>	<p>Several joints appear open.</p>	<p>Joint should be repaired.</p>

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
<p>CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT (Direction: looking d/s)</p>	<p>Downstream culvert concrete spalled on left & right entrance walls of culvert (2 in X 1 ft X 8 ft and 4 in X 8 in X 1.5 ft, respectively).</p>	<p>Spalled concrete areas should be repaired.</p>
<p>INTAKE STRUCTURE</p>	<p>Appears satisfactory.</p>	
<p>OUTLET STRUCTURE</p>	<p>Concrete spalled on two outlet chambers, left most outlet chamber spalled on three sides and second to right spalled on two opposite sides.</p>	<p>Spalled concrete should be repaired.</p>
<p>OUTLET CHANNEL (Direction: looking d/s)</p>	<p>Appears satisfactory.</p>	
<p>EMERGENCY GATE</p>	<p>None observed.</p>	<p>Alarm system & emergency gate should be constructed.</p>

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARK OR RECOMMENDATIONS
SLOPES	Slopes vary from vertical stone walls in front of homes to 1(V) to 10 (H) along soil slopes. Several eroded areas up to 4 in deep and in excess of 20 ft in length observed. In excess of 5 trees overhanging slopes and soil is eroded beneath.	Eroded areas should be suitably repaired.
SEDIMENTATION	Bottles, paper, cans in reservoir. Amount of sedimentation not determined. Non observed.	Debris should be removed.

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SPILLWAY CREST	Construction joints opened in excess of 1 in downstream. Flash boards appear 12 in in height above crest. Alignment appears satisfactory.	Joints should be suitably repaired.
APPROACH CHANNEL	Appears satisfactory.	
DISCHARGE CHANNEL	Wood and cans in channel.	Debris should be removed.
BRIDGE AND PIERS		

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	Concrete spalled in more than 1 area and spalled to depths of $\frac{1}{4}$ in to 1 in.	Spalled concrete areas should be suitably repaired.
APPROACH CHANNEL	Wood, styrofoam cups, baseball, leaves and cans in channel.	Debris should be removed.
DISCHARGE CHANNEL	Connects to ungated spillway.	
BRIDGE AND PIERS	A concrete conduit runs under roadway downstream.	
GATES AND OPERATION EQUIPMENT	4 Coffin manufactured valves stems with crank operators in gatehouse. Concrete below base plates cracked on all four operators.	Cracks should be checked for depth and repaired.

APPENDIX 3

PHOTOGRAPHS

LAKE MUSCONETCONG DAM




Dam (Route 206).
Looking downstream.

7 December 1978




Spillway. Looking west.


7 December 1978



Spillway. Looking east from 7 December 1978
gatehouse.




Debris in spillway. 7 December 1978



Spalled and cracked concrete and timber riser on crest of spillway.

7 December 1978



Upstream entrance to gatehouse. 7 December 1978



Deteriorated riprap at right abutment. 7 December 1978



Discharge from gatehouse into spillway channel. Note deteriorated concrete. 7 December 1978



Spalled concrete at upstream side of culvert under Route 206. 7 December 1978



Culvert under Route 206. Looking upstream. 7 December 1978



Erosion and spalled concrete 7 December 1978
at right sidewall below culvert
under Route 206.




Discharge channel. 7 December 1978
Looking downstream.



Left abutment area.
Looking south.

7 December 1978



Spalled concrete at end wall
of spillway channel. Note
absence of riprap.

7 December 1978

0

APPENDIX 4

HYDROLOGIC COMPUTATIONS

LAKE MUSCONETCONG DAM

0

HYDROLOGIC COMPUTATIONS
LAKE MUSCONETCONG DAM

Location : Morris - Sussex County, N.J.

Drainage Area : 30.3 sq. mi — [25.4 sq. mi to Lake Hopatcong
4.9 sq. mi to Lake Musconetcong proper]

Lake Area : 307 Acres

Classification : size - Intermediate
Hazard - High

Spillway Design Flood

Based on available information, it is understood that the spillway and gates have been designed on the basis of the flood of Oct. 1903. In accordance with the evaluation criteria, PMF should be used.

COMPUTE PMF

1. Dam located in Zone 6

PMF = 22.4 inches (200 sq. mi in 24 hrs.)

2. PMF must be adjusted for basin size

<u>Duration - hr</u>	<u>% Factor (for 100 sq. mi)</u>	<u>Reduction Factor*</u>
0-6	112	0.80
0-12	123	
0-24	132	
0-48	142	
		* p. 6 of "D.S.D"

3. Methodology

a) PMF be calculated using HEC-1 with Snyder Coefficients $C_t = 3.70$ and $C_p = 0.58$ recommended the Army Corp of Engineers.

b) Within Lake Musconetcong's drainage basin lies Lake Hopatcong. The outflow hydrograph from Lake Hopatcong is combined with the local inflow from the remaining drainage area to develop the inflow hydrograph for Lake Musconetcong and subsequent routing. (See schematic network next pg.)

UNIT HYDROGRAPH

Corp of Engineers has indicated that Snyder Method be used to develop local inflow for Lake Musconetcong's intermediate drainage area.

Snyder Lag time =

$$t_p = C_t (L \cdot L_{ca})^{0.3}$$

from drainage area

$$L = 20350 \text{ ft} \doteq 3.85 \text{ mi}$$

$$L_{ca} = 6850 \text{ ft} = 1.30 \text{ mi}$$

$$\therefore t_p = 3.7 (3.85 \times 1.30)^{0.3} \doteq 6.0 \text{ hrs.}$$

$$\therefore \underline{t_p = 6 \text{ hrs. and } C_p = 0.58 \text{ (given)}}$$




Catchment Basin




- Ⓐ - Hopatcong Subbasin
- Ⓑ - Musconetcong Subbasin


Schematic Network




SPILLWAY CAPACITY



Outflow discharge is first governed by the spillway. As discharge increases, the headwater in the culvert rises. Eventually the headwater rises to the same elevation as the spillway and top of culvert. At this time the culvert entrance is filled and the spillway is submerged. Discharge capacity will be governed by the culvert if its capacity is less than that of the submerged spillway.



Culvert Entrance



Discharge capacity of Culvert when spillway just becomes submerged or spillway discharge chamber filled (headwater for culvert at 859.75) :

'Open-Channel Hydraulics' by Chow, 1959
Fig. 17-29 on pg. 498.

$$\frac{H}{d} = 1, d = 11', \text{ then } Q/b = 120$$

$$\therefore Q = 120 \times 20 = 2400 \text{ cfs}$$

Approximate head above spillway when culvert entrance filled

$$H = \left(\frac{Q}{CL} \right)^{2/3}$$

$$= \left(\frac{2400}{3.3 \times 203} \right)^{2/3}$$

$$= 2.34 \text{ ft.}$$

Choose $C = 3.3$ (Table 5-3 of


'Handbook of Hydraulics' by King & Brater)

Elevation at two end of the retaining wall is approximately 863.5. Assume discharge obeys weir equation when overtop.

Use $C_{ag} = 2.5$ and $L = 200'$

Use $C_{ag} = 2.7$ for retaining wall portion which is at El. 864.

Length of retaining wall = 233'



Profile Section along retaining wall


Elevation (ft)	Spillway		Culvert			Two ends of dam		Retaining wall		Total (cfs) $Q_T = Q_C + Q_E + Q_R$
	H (ft)	C	H (ft)	H _d	D/b	H (ft)	Q _E (cfs)	H (ft)	Q _R (cfs)	
859.75	0									0
860.75	1	2.98	4.62	0.45	30		605			605
861.75	2	3.30	9.9	0.9	45		1895			1895
862.75	3	3.32	14	1.27	170		3400			3400
863.50	3.5		14.75	1.34	173		3460	0		3460
864.00	4.25		15.75	1.43	176		3520	0.5	177	3697
865.00	5.25		16.75	1.52	180		3600	1.5	919	5148
866.00	6.25		17.25	1.57	184		3780	2.5	1976	7535
867.00	7.25		18.25	1.66	192		3840	3.5	3274	10383
868.00	8.25		19.25	1.75	200		4000	4.5	4773	13806

Controlled Culvert

$Q_S = 203CH^{3/2}$, $Q_E = 500H^{3/2}$, $Q_R = 629.1H^{3/2}$

Q_C obtained from Fig. 17-29 on Pg. 498 of 'Open-Channel Hydraulics' by Chow

SPILLWAY RATING CURVE (Lake Musconetcong)



Reservoir Storage Capacity

Assume a linear distribution for the area of the lake with elevation. Start at a zero storage at the crest of the spillway.

Area of Lake = 307 Ac.

Perimeter of lake = 24,000 ft (measured from U.S.G.S. map)

Since perimeter is estimated from U.S.G.S. map, for estimated analysis purpose, it is assumed to be constant within the working elevation range.

Take average side slope = 1V : 6H.

∴ for every foot of water above the crest of spillway the area of lake increases by = $\frac{6(24000)}{43560} \approx 3 \text{ ac.}$


<u>Elev.</u> <u>(ft)</u>	<u>H</u> <u>(ft)</u>	<u>Increase in</u> <u>lake area (Acres)</u>	<u>Area of</u> <u>lake (Acres)</u>
859.75	0		307
860.75	1	3	310
861.75	2	6	313
862.75	3	9	316
863.75	4	12	319
864.75	5	15	322
865.75	6	18	325
866.75	7	21	328
867.75	8	24	331
868.75	9	27	334

SUMMARY OF HYDROGRAPH AND FLOOD ROUTING

1. Hydrograph and routing calculated using HEC-1
2. PMF for Lake Musconetcong is 6140 cfs
(routed to 5948 cfs)
3. Routing indicates the two ends of the dam will overtop by approximately 1.8 ft and the retaining wall running parallel to the roadway will overtop by approximately 1.3 ft for PMF.

OVERTOPPING POTENTIAL

1. Various % of PMF have been routed using HEC-1
2. Plot peak outflow vs % PMF



3. Dam overtops at approx. El. 863.5 with $Q = 3460$ cfs.
∴ dam can pass approx. 71% of PMF.

DRAWDOWN ANALYSIS

1. Outlet structures

- 4 - 3' x 5' sluiceways
- 1 - 36" pipe that leads to the canal.

2. Outlet Capacity

- Sill of gates at El. 850.0
- Top of gates at El. 855.0
- 2 of 36" pipe at El. 856.0

Consider pipe discharge when pool elevation is above El. 856.0, Assume orifice flow.

When pool elevation is above El. 855.0, gate discharge is governed by orifice flow. As pool elevation is lowered below El. 855.0, gate discharge is governed by weir flow. Use $C = 3.33$ for weir flow and $C = 0.62$ for orifice flow for the gates (available original design data) Use $C = 0.6$ for pipe.

Elev. (ft.)	Gates		36" pipe		Q_T (cfs)	$Q_{ave.}$ (cfs)
	Head (ft)	Q_g (cfs)	Head (ft)	Q_p (cfs)		
860	7.5	817	4	68	885	852
859	6.5	761	3	59	820	784
858	5.5	700	2	48	748	598
857	4.5	633	1	34	667	613
856	3.5	558	0	0	558	503
855	5	447			447	384
854	4	320			320	264
853	3	208			208	161
852	2	113			113	77
851	1	40			40	20
850	0	0			0	

3. Storage Capacity

a. Estimated usable storage above the lowest elevation of the gates is 1800 ac-ft.

b. Assume area varies linearly with height,
Area of lake at bottom of gates = 53 acres

Elev.	Area (Ac)	Δ Storage (ac-ft)	Total Storage (Ac-ft)
860	307	295	1800
859	282	269	
858	256	244	
857	231	218	
856	205	180	
855	180	168	
854	155	142	
853	129	117	
852	104	91	
851	78	66	
850	53		

4. Assume in flow to be 2 cfs/sq. mi


$$Q_{in} = 30.3 \times 2 = 60.6 \text{ cfs}$$

Elev. (ft)	Q _{out} area (cfs)	Q _{net} * (cfs)	Δ Storage (Ac-ft)	Δt (hr.)	Σ Δt (hr)	
860	852	791	295	4.5		
859	784	723	269	4.5		
858	598	537	244	5.5		
857	613	552	218	4.8		
856	503	442	180	4.9	24.2	(1 day)
855	384	323	168	6.3		
854	264	203	142	8.5		
853	161	100	117	14.2		
852	77	16	91	68.8	122	5 days
851	20	-**	-			
850						

* $Q_{net} = Q_{out \text{ area}} - Q_{in} = Q_{out \text{ area}} - 61$


** $Q_{in} > Q_{out}$ not considered.


Lake can be lowered 5 feet in about 1 day
and 9 feet in about 5 days


















MAP SOURCE: U.S.G.S.
DOVER, FRANKLIN, NEWTON EAST, STANHOPE
SCALE 1" = 2000'

DRAINAGE BASIN

LAKE MUSCONETONG

LANSAN ENGINEERING ASSOCIATES, INC.

1000 WASHINGTON AVENUE, S.W. WASHINGTON, D.C. 20004

HEC-1 OUTPUT

LAKE MUSCONETCONG DAM

41
42
43
44

SE859.75 860.75 861.75 862.75 863.75 864.75 865.75 866.75 867.75 868.75
\$859.75
\$D863.50
K

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT 1
ROUTE HYDROGRAPH TO 2
RUNOFF HYDROGRAPH AT 2
COMBINE 2 HYDROGRAPHS AT 2
ROUTE HYDROGRAPH TO 3
END OF NETWORK

1*****
FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 25 SEP 78

RUN DATE# 79/02/05.
TIME# 17.31.04.

LAKE MUSCONETCONG DAM
INFLOW HYDROGRAPH AND ROUTING
N.J. DAM INSPECTION

NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
150	1	0	0	0	0	0	0	0	0
			JOPER	NWT	LROPT	TRACE			
			3	0	0	0			

JOB SPECIFICATION

SUB-AREA RUNOFF COMPUTATION

COMPUTE HYDROGRAPH - HOPATCONG LOCAL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	0	0	0	0	0	1	0	0

IHYDG	IUHG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	25.40	0.00	25.40	.82	0.000	0	0	0

PRECIP DATA

1.02	1.00	1.12	0.00	.12	541.	1.05	4.00	100	0.00	0.00	0.00	409.
1.02	2.00	.12	0.00	.12	571.	1.05	5.00	101	0.00	0.00	0.00	382.
1.02	3.00	.12	0.00	.12	587.	1.05	6.00	102	0.00	0.00	0.00	357.
1.02	4.00	.12	0.00	.12	587.	1.05	7.00	103	0.00	0.00	0.00	334.
1.02	5.00	.12	0.00	.12	565.	1.05	8.00	104	0.00	0.00	0.00	312.
1.02	6.00	.12	0.00	.12	531.	1.05	9.00	105	0.00	0.00	0.00	293.
1.02	7.00	.13	.28	.15	498.	1.05	10.00	106	0.00	0.00	0.00	274.
1.02	8.00	.13	.28	.15	474.	1.05	11.00	107	0.00	0.00	0.00	256.
1.02	9.00	.13	.28	.15	461.	1.05	12.00	108	0.00	0.00	0.00	240.
1.02	10.00	.13	.28	.15	461.	1.05	13.00	109	0.00	0.00	0.00	225.
1.02	11.00	.13	.28	.15	475.	1.05	14.00	110	0.00	0.00	0.00	211.
1.02	12.00	.13	.28	.15	503.	1.05	15.00	111	0.00	0.00	0.00	198.
1.02	13.00	.13	.28	.15	578.	1.05	16.00	112	0.00	0.00	0.00	177.
1.02	14.00	.13	.28	.15	757.	1.05	17.00	113	0.00	0.00	0.00	154.
1.02	15.00	.13	.28	.15	1097.	1.05	18.00	114	0.00	0.00	0.00	131.
1.02	16.00	.13	.28	.15	1725.	1.05	19.00	115	0.00	0.00	0.00	82.
1.02	17.00	.13	.28	.15	2730.	1.05	20.00	116	0.00	0.00	0.00	65.
1.02	18.00	.13	.28	.15	4062.	1.05	21.00	117	0.00	0.00	0.00	52.
1.02	19.00	.13	.28	.15	5633.	1.05	22.00	118	0.00	0.00	0.00	52.
1.02	20.00	.13	.28	.15	7335.	1.05	23.00	119	0.00	0.00	0.00	52.
1.02	21.00	.13	.28	.15	9074.	1.06	0.00	120	0.00	0.00	0.00	52.
1.02	22.00	.13	.28	.15	10763.	1.06	1.00	121	0.00	0.00	0.00	51.
1.02	23.00	.13	.28	.15	12283.	1.06	2.00	122	0.00	0.00	0.00	51.
1.03	0.00	.18	.03	.15	13526.	1.06	3.00	123	0.00	0.00	0.00	51.
1.03	1.00	.18	.03	.15	14425.	1.06	4.00	124	0.00	0.00	0.00	51.
1.03	2.00	.18	.03	.15	14928.	1.06	5.00	125	0.00	0.00	0.00	51.
1.03	3.00	.18	.03	.15	15026.	1.06	6.00	126	0.00	0.00	0.00	51.
1.03	4.00	.18	.03	.15	14725.	1.06	7.00	127	0.00	0.00	0.00	51.
1.03	5.00	.18	.03	.15	14055.	1.06	8.00	128	0.00	0.00	0.00	51.
1.03	6.00	.18	.03	.15	13170.	1.06	9.00	129	0.00	0.00	0.00	51.
1.03	7.00	.18	.03	.15	12236.	1.06	10.00	130	0.00	0.00	0.00	51.
1.03	8.00	.18	.03	.15	11334.	1.06	11.00	131	0.00	0.00	0.00	51.
1.03	9.00	.18	.03	.15	10495.	1.06	12.00	132	0.00	0.00	0.00	51.
1.03	10.00	.18	.03	.15	9716.	1.06	13.00	133	0.00	0.00	0.00	51.
1.03	11.00	.18	.03	.15	8992.	1.06	14.00	134	0.00	0.00	0.00	51.
1.03	12.00	.18	.03	.15	8321.	1.06	15.00	135	0.00	0.00	0.00	51.
1.03	13.00	.18	.03	.15	7698.	1.06	16.00	136	0.00	0.00	0.00	51.
1.03	14.00	.18	.03	.15	7121.	1.06	17.00	137	0.00	0.00	0.00	51.
1.03	15.00	.18	.03	.15	6588.	1.06	18.00	138	0.00	0.00	0.00	51.
1.03	16.00	.18	.03	.15	6095.	1.06	19.00	139	0.00	0.00	0.00	51.
1.03	17.00	.18	.03	.15	5640.	1.06	20.00	140	0.00	0.00	0.00	51.
1.03	18.00	.18	.03	.15	5218.	1.06	21.00	141	0.00	0.00	0.00	51.
1.03	19.00	.18	.03	.15	4829.	1.06	22.00	142	0.00	0.00	0.00	51.
1.03	20.00	.18	.03	.15	4469.	1.06	23.00	143	0.00	0.00	0.00	51.
1.03	21.00	.18	.03	.15	4136.	1.07	0.00	144	0.00	0.00	0.00	51.
1.03	22.00	.18	.03	.15	3828.	1.07	1.00	145	0.00	0.00	0.00	51.
1.03	23.00	.18	.03	.15	3543.	1.07	2.00	146	0.00	0.00	0.00	51.
1.04	0.00	.18	.03	.15	3280.	1.07	3.00	147	0.00	0.00	0.00	51.
1.04	1.00	.18	.03	.15	3036.	1.07	4.00	148	0.00	0.00	0.00	51.
1.04	2.00	.18	.03	.15	2603.	1.07	5.00	149	0.00	0.00	0.00	51.
1.04	3.00	.18	.03	.15	2603.	1.07	6.00	150	0.00	0.00	0.00	51.

SUM 24.80 19.82 4.98 330800.
 (630.) (503.) (126.) (9367.21)

PEAK 15026. 14418. 408. 425.
 CFS 10167. 4450. 126. 9365.
 CMS 288. 126. 9365.
 INCHES 14.89 19.56 20.19
 MM 378.29 496.79 512.77
 AC-FT 7149. 20165. 27334.
 THOUS CU M 8819. 24873. 32665. 33716.

HYDROGRAPH ROUTING

ROUTING COMPUTATIONS - HOPATCONG

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO	
2	1	0	0	0	0	1	0	0	
ROUTING DATA									
QLOSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR		
0.0	0.000	0.00	1	0	0	0	0		
NSTPS NSTDL LAG AMSKK X TSK STORA ISPRAT									
1	0	0	0.000	0.000	0.000	0.000	0.	-1	
STAGE	923.30	924.30	925.30	926.30	927.70	928.70	929.70	930.70	931.70
FLOW	0.00	333.00	942.00	1730.00	3073.00	4497.00	6291.00	8355.00	10651.00
SURFACE AREA=	2474.	2491.	2508.	2525.	2542.	2559.	2576.	2593.	2627.
	2644.	2661.							
CAPACITY=	0.	2482.	4982.	7498.	10032.	12582.	15150.	17734.	20336.
	25590.								
ELEVATION=	923.	924.	925.	926.	927.	928.	929.	930.	931.
	933.	934.							

CREL 923.3 0.0
 SPWID 0.0
 COOW 0.0
 EXPW 0.0
 ELEVEL 0.0
 COOL 0.0
 CAREA 0.0
 EXPL 0.0

DAM DATA
 TOPEL 927.7
 COQD 0.0
 EXPD 0.0
 DAMWID 0.0

MO. DA	HR. MN	END-OF-PERIOD HYDROGRAPH ORDINATES			STAGE	
		PERIOD	HOURS	INFLOW		OUTFLOW
1.01	1.00	1	1.00	51.	1.	4.
1.01	2.00	2	2.00	51.	1.	8.
1.01	3.00	3	3.00	51.	2.	12.
1.01	4.00	4	4.00	51.	2.	16.
1.01	5.00	5	5.00	51.	3.	20.
1.01	6.00	6	6.00	51.	3.	24.
1.01	7.00	7	7.00	51.	4.	28.
1.01	8.00	8	8.00	51.	4.	32.
1.01	9.00	9	9.00	51.	5.	36.
1.01	10.00	10	10.00	51.	5.	40.
1.01	11.00	11	11.00	51.	6.	43.
1.01	12.00	12	12.00	51.	6.	47.
1.01	13.00	13	13.00	51.	7.	51.
1.01	14.00	14	14.00	51.	7.	54.
1.01	15.00	15	15.00	51.	8.	58.
1.01	16.00	16	16.00	60.	8.	62.
1.01	17.00	17	17.00	88.	9.	67.
1.01	18.00	18	18.00	131.	10.	76.
1.01	19.00	19	19.00	184.	12.	88.
1.01	20.00	20	20.00	245.	14.	104.
1.01	21.00	21	21.00	310.	17.	126.
1.01	22.00	22	22.00	378.	21.	153.
1.01	23.00	23	23.00	443.	25.	185.
1.02	0.00	24	24.00	498.	30.	221.
1.02	1.00	25	25.00	541.	35.	262.
1.02	2.00	26	26.00	571.	41.	305.
1.02	3.00	27	27.00	587.	47.	349.
1.02	4.00	28	28.00	587.	53.	393.
1.02	5.00	29	29.00	565.	59.	436.
1.02	6.00	30	30.00	531.	64.	476.
1.02	7.00	31	31.00	498.	69.	513.
1.02	8.00	32	32.00	474.	74.	548.
1.02	9.00	33	33.00	461.	78.	580.
1.02	10.00	34	34.00	461.	82.	611.
1.02	11.00	35	35.00	475.	86.	643.
1.02	12.00	36	36.00	503.	91.	676.
1.02	13.00	37	37.00	578.	96.	713.
1.02	14.00	38	38.00	757.	102.	760.
1.02	15.00	39	39.00	1097.	111.	828.
1.02	16.00	40	40.00	1725.	126.	935.
1.02	17.00	41	41.00	2730.	149.	1107.
1.02	18.00	42	42.00	4062.	185.	1374.
1.02	19.00	43	43.00	5633.	236.	1758.
1.02	20.00	44	44.00	7335.	305.	2271.
1.02	21.00	45	45.00	9074.	440.	2918.
1.02	22.00	46	46.00	10763.	629.	3694.
1.02	23.00	47	47.00	12283.	846.	4585.

1.03	1.00	49	49.00	14425.	1447.	6619.	345.0
1.03	2.00	50	50.00	14928.	1455.	6619.	926.0
1.03	3.00	51	51.00	15026.	1805.	7697.	926.4
1.03	4.00	52	52.00	14725.	2212.	8769.	926.8
1.03	5.00	53	53.00	14055.	2601.	9799.	927.2
1.03	6.00	54	54.00	13170.	2963.	10758.	927.6
1.03	7.00	55	55.00	12236.	3392.	11621.	927.9
1.03	8.00	56	56.00	11334.	3811.	12373.	928.2
1.03	9.00	57	57.00	10495.	4169.	13017.	928.5
1.03	10.00	58	58.00	9716.	4472.	13562.	928.7
1.03	11.00	59	59.00	8992.	4782.	14015.	928.9
1.03	12.00	60	60.00	8321.	5038.	14382.	929.0
1.03	13.00	61	61.00	7698.	5241.	14673.	929.1
1.03	14.00	62	62.00	7121.	5396.	14895.	929.2
1.03	15.00	63	63.00	6588.	5509.	15057.	929.3
1.03	16.00	64	64.00	6095.	5584.	15165.	929.3
1.03	17.00	64	64.00	6095.	5626.	15226.	929.3
1.03	18.00	66	66.00	5218.	65.00	5640.	5640.
1.03	19.00	67	67.00	4829.	5628.	5628.	929.3
1.03	20.00	68	68.00	4469.	5594.	5594.	929.3
1.03	21.00	69	69.00	4136.	5541.	5541.	929.3
1.03	22.00	70	70.00	3828.	5472.	5504.	929.2
1.03	23.00	71	71.00	3543.	5389.	5504.	929.2
1.04	0.00	72	72.00	3280.	5293.	5485.	929.1
1.04	1.00	73	73.00	3036.	5188.	5497.	929.1
1.04	2.00	74	74.00	2811.	5074.	5434.	929.0
1.04	3.00	75	75.00	2603.	4954.	5426.	929.0
1.04	4.00	76	76.00	2411.	4828.	5408.	928.9
1.04	5.00	77	77.00	2233.	4697.	5389.	928.8
1.04	6.00	78	78.00	2068.	4564.	5370.	928.7
1.04	7.00	79	79.00	1916.	4442.	5350.	928.7
1.04	8.00	80	80.00	1776.	4332.	5311.	928.6
1.04	9.00	81	81.00	1646.	4221.	5310.	928.5
1.04	10.00	82	82.00	1525.	4108.	5290.	928.4
1.04	11.00	83	83.00	1414.	3995.	5270.	928.3
1.04	12.00	84	84.00	1311.	3881.	5250.	928.3
1.04	13.00	85	85.00	1216.	3768.	5229.	928.2
1.04	14.00	86	86.00	1129.	3655.	5209.	928.1
1.04	15.00	87	87.00	1047.	3544.	5189.	928.0
1.04	16.00	88	88.00	972.	3433.	5169.	928.0
1.04	17.00	89	89.00	903.	3324.	5149.	927.9
1.04	18.00	90	90.00	838.	3216.	5130.	927.8
1.04	19.00	91	91.00	776.	3110.	5117.	927.7
1.04	20.00	92	92.00	721.	3028.	5093.	927.7
1.04	21.00	93	93.00	670.	2958.	5074.	927.6
1.04	22.00	94	94.00	623.	2889.	5056.	927.5
1.04	23.00	95	95.00	580.	2820.	5037.	927.4
1.05	0.00	96	96.00	540.	2752.	5019.	927.4
1.05	1.00	97	97.00	503.	2684.	5019.	927.3
1.05	2.00	98	98.00	469.	2618.	5043.	927.2
1.05	3.00	98	98.00	469.	2553.	9670.	927.2

929.3

15245.

5640.

65 17.00

1.00 0.00 100 100.00 01. /38. 0184. 945.0

PEAK OUTFLOW IS 5640. AT TIME 65.00 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	5640.	5600.	5103.	3406.	280676.
CMS	160.	159.	145.	96.	7948.
INCHES	2.05	7.48	14.97	17.13	435.16
MM	52.09	189.89	380.21	20268.	23196.
AC-FT	2777.	10122.	20268.	25000.	28612.
THOUS CU M	3425.	12486.	25000.		

SUB-AREA RUNOFF COMPUTATION

COMPUTE HYDROGRAPH - MUSCONETCONG LOCAL

IHYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RAUTO	ISNOW	ISAME	LOCAL
1	1	4.90	0.00	4.90	.80	0.000	0	0	0

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2	0	0	0	0	0	1	0	0

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	22.40	112.00	123.00	132.00	142.00	0.00	0.00

PRECIP DATA

LOSS DATA

LROPT STRKR DLTKR RTIOL ERRAIN STRKS RTIOK STRTL CNSTL ALSMX RTIMP
 0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .15 0.00 0.00

UNIT HYDROGRAPH DATA
 TP= 6.00 CP= .58 NTA= 0

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 6.77 AND R= 6.15 INTERVALS

RECESSION DATA
 STRTQ= -2.00 QRCNSN= 0.00 RTIOR= 1.00
 19. 140. 214. 276. 309. 308. 274. 233. 198.
 100 100 100 100 100 100 100 100 100

UNIT HYDROGRAPH 37 END-OF-PERIOD ORDINATES, LAG= 6.00 HOURS, CP= .58 VOL= 1.00
 100 100 100 100 100 100 100 100 100

MO. DA		HR. MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW		NO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW		NO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
							COMP Q								COMP Q								
1.01	1.01	1.00	1	.01	0.00	.01	10.	1.04	4.00	76	0.00	0.00	0.00	0.00	10.	1.04	4.00	76	0.00	0.00	0.00	0.00	43.
1.01	1.01	2.00	2	.01	0.00	.01	10.	1.04	5.00	77	0.00	0.00	0.00	0.00	10.	1.04	5.00	77	0.00	0.00	0.00	0.00	23.
1.01	1.01	3.00	3	.01	0.00	.01	10.	1.04	6.00	78	0.00	0.00	0.00	0.00	10.	1.04	6.00	78	0.00	0.00	0.00	0.00	15.
1.01	1.01	4.00	4	.01	0.00	.01	10.	1.04	7.00	79	0.00	0.00	0.00	0.00	10.	1.04	7.00	79	0.00	0.00	0.00	0.00	10.
1.01	1.01	5.00	5	.01	0.00	.01	10.	1.04	8.00	80	0.00	0.00	0.00	0.00	10.	1.04	8.00	80	0.00	0.00	0.00	0.00	10.
1.01	1.01	6.00	6	.01	0.00	.01	10.	1.04	9.00	81	0.00	0.00	0.00	0.00	10.	1.04	9.00	81	0.00	0.00	0.00	0.00	10.
1.01	1.01	7.00	7	.02	0.00	.02	10.	1.04	10.00	82	0.00	0.00	0.00	0.00	10.	1.04	10.00	82	0.00	0.00	0.00	0.00	10.
1.01	1.01	8.00	8	.02	0.00	.02	10.	1.04	11.00	83	0.00	0.00	0.00	0.00	10.	1.04	11.00	83	0.00	0.00	0.00	0.00	10.
1.01	1.01	9.00	9	.02	0.00	.02	10.	1.04	12.00	84	0.00	0.00	0.00	0.00	10.	1.04	12.00	84	0.00	0.00	0.00	0.00	10.
1.01	1.01	10.00	10	.02	0.00	.02	10.	1.04	13.00	85	0.00	0.00	0.00	0.00	10.	1.04	13.00	85	0.00	0.00	0.00	0.00	10.
1.01	1.01	11.00	11	.02	0.00	.02	10.	1.04	14.00	86	0.00	0.00	0.00	0.00	10.	1.04	14.00	86	0.00	0.00	0.00	0.00	10.
1.01	1.01	12.00	12	.02	0.00	.02	10.	1.04	15.00	87	0.00	0.00	0.00	0.00	10.	1.04	15.00	87	0.00	0.00	0.00	0.00	10.
1.01	1.01	13.00	13	.15	0.00	.15	10.	1.04	16.00	88	0.00	0.00	0.00	0.00	10.	1.04	16.00	88	0.00	0.00	0.00	0.00	10.
1.01	1.01	14.00	14	.18	0.00	.18	10.	1.04	17.00	89	0.00	0.00	0.00	0.00	10.	1.04	17.00	89	0.00	0.00	0.00	0.00	10.
1.01	1.01	15.00	15	.23	0.00	.23	10.	1.04	18.00	90	0.00	0.00	0.00	0.00	10.	1.04	18.00	90	0.00	0.00	0.00	0.00	10.
1.01	1.01	16.00	16	.58	.25	.33	15.	1.04	19.00	91	0.00	0.00	0.00	0.00	10.	1.04	19.00	91	0.00	0.00	0.00	0.00	10.
1.01	1.01	17.00	17	.21	.06	.15	29.	1.04	20.00	92	0.00	0.00	0.00	0.00	10.	1.04	20.00	92	0.00	0.00	0.00	0.00	10.
1.01	1.01	18.00	18	.17	.02	.15	50.	1.04	21.00	93	0.00	0.00	0.00	0.00	10.	1.04	21.00	93	0.00	0.00	0.00	0.00	10.
1.01	1.01	19.00	19	.01	0.00	.01	73.	1.04	22.00	94	0.00	0.00	0.00	0.00	10.	1.04	22.00	94	0.00	0.00	0.00	0.00	10.
1.01	1.01	20.00	20	.01	0.00	.01	95.	1.04	23.00	95	0.00	0.00	0.00	0.00	10.	1.04	23.00	95	0.00	0.00	0.00	0.00	10.
1.01	1.01	21.00	21	.01	0.00	.01	108.	1.05	0.00	96	0.00	0.00	0.00	0.00	10.	1.05	0.00	96	0.00	0.00	0.00	0.00	10.
1.01	1.01	22.00	22	.01	0.00	.01	111.	1.05	1.00	97	0.00	0.00	0.00	0.00	10.	1.05	1.00	97	0.00	0.00	0.00	0.00	10.
1.01	1.01	23.00	23	.01	0.00	.01	103.	1.05	2.00	98	0.00	0.00	0.00	0.00	10.	1.05	2.00	98	0.00	0.00	0.00	0.00	10.
1.02	1.02	0.00	24	.01	0.00	.01	91.	1.05	3.00	99	0.00	0.00	0.00	0.00	10.	1.05	3.00	99	0.00	0.00	0.00	0.00	10.
1.02	1.02	1.00	25	.11	0.00	.11	79.	1.05	4.00	100	0.00	0.00	0.00	0.00	10.	1.05	4.00	100	0.00	0.00	0.00	0.00	10.
1.02	1.02	2.00	26	.11	0.00	.11	68.	1.05	5.00	101	0.00	0.00	0.00	0.00	10.	1.05	5.00	101	0.00	0.00	0.00	0.00	10.
1.02	1.02	3.00	27	.11	0.00	.11	60.	1.05	6.00	102	0.00	0.00	0.00	0.00	10.	1.05	6.00	102	0.00	0.00	0.00	0.00	10.
1.02	1.02	4.00	28	.11	0.00	.11	52.	1.05	7.00	103	0.00	0.00	0.00	0.00	10.	1.05	7.00	103	0.00	0.00	0.00	0.00	10.
1.02	1.02	5.00	29	.11	0.00	.11	46.	1.05	8.00	104	0.00	0.00	0.00	0.00	10.	1.05	8.00	104	0.00	0.00	0.00	0.00	10.
1.02	1.02	6.00	30	.11	0.00	.11	40.	1.05	9.00	105	0.00	0.00	0.00	0.00	10.	1.05	9.00	105	0.00	0.00	0.00	0.00	10.
1.02	1.02	7.00	31	.33	.18	.15	39.	1.05	10.00	106	0.00	0.00	0.00	0.00	10.	1.05	10.00	106	0.00	0.00	0.00	0.00	10.
1.02	1.02	8.00	32	.33	.18	.15	48.	1.05	11.00	107	0.00	0.00	0.00	0.00	10.	1.05	11.00	107	0.00	0.00	0.00	0.00	10.
1.02	1.02	9.00	33	.33	.18	.15	69.	1.05	12.00	108	0.00	0.00	0.00	0.00	10.	1.05	12.00	108	0.00	0.00	0.00	0.00	10.
1.02	1.02	10.00	34	.33	.18	.15	105.	1.05	13.00	109	0.00	0.00	0.00	0.00	10.	1.05	13.00	109	0.00	0.00	0.00	0.00	10.
1.02	1.02	11.00	35	.33	.18	.15	152.	1.05	14.00	110	0.00	0.00	0.00	0.00	10.	1.05	14.00	110	0.00	0.00	0.00	0.00	10.
1.02	1.02	12.00	36	.33	.18	.15	205.	1.05	15.00	111	0.00	0.00	0.00	0.00	10.	1.05	15.00	111	0.00	0.00	0.00	0.00	10.
1.02	1.02	13.00	37	.33	.18	.15	290.	1.05	16.00	112	0.00	0.00	0.00	0.00	10.	1.05	16.00	112	0.00	0.00	0.00	0.00	10.
1.02	1.02	14.00	38	2.41	1.86	.15	463.	1.05	17.00	113	0.00	0.00	0.00	0.00	10.	1.05	17.00	113	0.00	0.00	0.00	0.00	10.
1.02	1.02	15.00	39	3.01	2.26	.15	777.	1.05	18.00	114	0.00	0.00	0.00	0.00	10.	1.05	18.00	114	0.00	0.00	0.00	0.00	10.
1.02	1.02	16.00	40	7.63	7.48	.15	1357.	1.05	19.00	115	0.00	0.00	0.00	0.00	10.	1.05	19.00	115	0.00	0.00	0.00	0.00	10.
1.02	1.02	17.00	41	2.81	2.66	.15	2251.	1.05	20.00	116	0.00	0.00	0.00	0.00	10.	1.05	20.00	116	0.00	0.00	0.00	0.00	10.
1.02	1.02	18.00	42	2.21	2.06	.15	3329.	1.05	21.00	117	0.00	0.00	0.00	0.00	10.	1.05	21.00	117	0.00	0.00	0.00	0.00	10.
1.02	1.02	19.00	43	.16	.01	.15	4392.	1.05	22.00	118	0.00	0.00	0.00	0.00	10.	1.05	22.00	118	0.00	0.00	0.00	0.00	10.
1.02	1.02	20.00	44	.16	.01	.15	5193.	1.05	23.00	119	0.00	0.00	0.00	0.00	10.	1.05	23.00	119	0.00	0.00	0.00	0.00	10.

1.02	22.00	.12	.01	.12	3200.	1.00	U.00	120	U.00	0.00	10.
1.02	23.00	.15	.01	.15	5511.	1.06	2.00	121	0.00	0.00	10.
1.03	0.00	.15	.01	.15	5059.	1.06	3.00	122	0.00	0.00	10.
1.03	1.00	0.00	0.00	0.00	4432.	1.06	4.00	123	0.00	0.00	10.
1.03	2.00	0.00	0.00	0.00	3798.	1.06	5.00	124	0.00	0.00	10.
1.03	3.00	0.00	0.00	0.00	3233.	1.06	6.00	125	0.00	0.00	10.
1.03	4.00	0.00	0.00	0.00	2752.	1.06	7.00	126	0.00	0.00	10.
1.03	5.00	0.00	0.00	0.00	2343.	1.06	8.00	127	0.00	0.00	10.
1.03	6.00	0.00	0.00	0.00	1993.	1.06	9.00	128	0.00	0.00	10.
1.03	7.00	0.00	0.00	0.00	1695.	1.06	10.00	129	0.00	0.00	10.
1.03	8.00	0.00	0.00	0.00	1442.	1.06	11.00	130	0.00	0.00	10.
1.03	9.00	0.00	0.00	0.00	1227.	1.06	12.00	131	0.00	0.00	10.
1.03	10.00	0.00	0.00	0.00	1044.	1.06	13.00	132	0.00	0.00	10.
1.03	11.00	0.00	0.00	0.00	888.	1.06	14.00	133	0.00	0.00	10.
1.03	12.00	0.00	0.00	0.00	756.	1.06	15.00	134	0.00	0.00	10.
1.03	13.00	0.00	0.00	0.00	644.	1.06	16.00	135	0.00	0.00	10.
1.03	14.00	0.00	0.00	0.00	549.	1.06	17.00	136	0.00	0.00	10.
1.03	15.00	0.00	0.00	0.00	468.	1.06	18.00	137	0.00	0.00	10.
1.03	16.00	0.00	0.00	0.00	399.	1.06	19.00	138	0.00	0.00	10.
1.03	17.00	0.00	0.00	0.00	340.	1.06	20.00	139	0.00	0.00	10.
1.03	18.00	0.00	0.00	0.00	291.	1.06	21.00	140	0.00	0.00	10.
1.03	19.00	0.00	0.00	0.00	248.	1.06	22.00	141	0.00	0.00	10.
1.03	20.00	0.00	0.00	0.00	213.	1.06	23.00	142	0.00	0.00	10.
1.03	21.00	0.00	0.00	0.00	182.	1.06	0.00	143	0.00	0.00	10.
1.03	22.00	0.00	0.00	0.00	155.	1.07	0.00	144	0.00	0.00	10.
1.03	23.00	0.00	0.00	0.00	133.	1.07	2.00	145	0.00	0.00	10.
1.04	0.00	0.00	0.00	0.00	114.	1.07	3.00	146	0.00	0.00	10.
1.04	1.00	0.00	0.00	0.00	98.	1.07	4.00	147	0.00	0.00	10.
1.04	2.00	0.00	0.00	0.00	85.	1.07	5.00	148	0.00	0.00	10.
1.04	3.00	0.00	0.00	0.00	69.	1.07	6.00	149	0.00	0.00	10.
1.04	3.00	0.00	0.00	0.00	56.	1.07	6.00	150	0.00	0.00	10.

SUM 25.45 20.64 4.81 66438.
 (646.) (524.) (122.) (1881.31)

CFS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
5580.	5580.	4978.	2530.	912.	66409.
158.	158.	141.	72.	26.	1880.
		9.45	19.21	20.77	21.01
		240.05	487.90	527.65	533.71
		2468.	5017.	5426.	5488.
		3045.	6189.	6693.	6770.

13

STAGE	859.75	860.75	861.75	862.75	863.50	864.00	865.00	866.00	867.00	0
FLOW	0.00	605.00	1895.00	3400.00	3460.00	3697.00	5148.00	7535.00	10383.00	0
SURFACE AREA=	307.	310.	313.	316.	319.	322.	325.	331.	334.	
CAPACITY=	0.	308.	620.	934.	1252.	1572.	1896.	2222.	2552.	2884.
ELEVATION=	860.	861.	862.	863.	864.	865.	866.	867.	868.	869.

CREL	SPWID	COQW	EXPN	ELEVL	COQL	CAREA	EXPL
859.8	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA

TOPEL	COQD	EXPD	DAMWID
863.5	0.0	0.0	0.

END-OF-PERIOD HYDROGRAPH ORDINATES

MO.DA	HR.MN	PERIOD	HOURS	INFLOW	OUTFLOW	STORAGE	STAGE
1.01	1.00	1	1.00	10.	2.	1.	859.8
1.01	2.00	2	2.00	11.	3.	1.	859.8
1.01	3.00	3	3.00	11.	4.	2.	859.8
1.01	4.00	4	4.00	12.	5.	3.	859.8
1.01	5.00	5	5.00	13.	6.	3.	859.8
1.01	6.00	6	6.00	13.	7.	4.	859.8
1.01	7.00	7	7.00	14.	8.	4.	859.8
1.01	8.00	8	8.00	14.	9.	5.	859.8
1.01	9.00	9	9.00	15.	10.	5.	859.8
1.01	10.00	10	10.00	15.	11.	5.	859.8
1.01	11.00	11	11.00	16.	11.	6.	859.8
1.01	12.00	12	12.00	16.	12.	6.	859.8
1.01	13.00	13	13.00	17.	13.	6.	859.8
1.01	14.00	14	14.00	17.	13.	7.	859.8
1.01	15.00	15	15.00	18.	14.	7.	859.8
1.01	16.00	16	16.00	23.	15.	8.	859.8
1.01	17.00	17	17.00	38.	17.	9.	859.8
1.01	18.00	18	18.00	60.	22.	11.	859.8
1.01	19.00	19	19.00	85.	30.	15.	859.8
1.01	20.00	20	20.00	109.	40.	20.	859.8
1.01	21.00	21	21.00	125.	51.	26.	859.8
1.01	22.00	22	22.00	132.	63.	32.	859.9
1.01	23.00	23	23.00	128.	73.	37.	859.9
1.02	0.00	24	24.00	121.	81.	41.	859.9
1.02	1.00	25	25.00	111.	86.	41.	859.9

AD-A067 766

LANGAN ENGINEERING ASSOCIATES INC CLIFTON NJ
NATIONAL DAM SAFETY PROGRAM. LAKE MUSCONETCONG
APR 79 D J LEARY


F/G 13/2
DAM(NJ00328). DE--ETC(U)
DACW61-78-C-0124
NL

UNCLASSIFIED

2 OF 2
AD
A067766



END
DATE
FILMED
6 -79
DDC



1.02	4.00	26	26.00	119.	89.	44.	859.9
1.02	3.00	27	27.00	109.	90.	46.	859.9
1.02	4.00	28	28.00	107.	93.	47.	859.9
1.02	5.00	29	29.00	105.	95.	48.	859.9
1.02	6.00	30	30.00	104.	96.	49.	859.9
1.02	7.00	31	31.00	104.	97.	49.	859.9
1.02	8.00	32	32.00	108.	99.	50.	859.9
1.02	9.00	33	33.00	121.	101.	51.	859.9
1.02	10.00	34	34.00	147.	106.	54.	859.9
1.02	11.00	35	35.00	187.	115.	59.	859.9
1.02	12.00	36	36.00	238.	130.	66.	860.0
1.02	13.00	37	37.00	296.	151.	76.	860.0
1.02	14.00	38	38.00	386.	175.	91.	860.0
1.02	15.00	39	39.00	565.	224.	114.	860.1
1.02	16.00	40	40.00	888.	299.	152.	860.2
1.02	17.00	41	41.00	1483.	432.	220.	860.5
1.02	18.00	42	42.00	2399.	708.	333.	860.8
1.02	19.00	43	43.00	3513.	1366.	492.	861.3
1.02	20.00	44	44.00	4628.	2190.	681.	861.9
1.02	21.00	45	45.00	5497.	3138.	880.	862.6
1.02	22.00	46	46.00	6019.	3438.	1084.	863.2
1.02	23.00	47	47.00	6140.	3640.	1294.	863.9
1.03	0.00	48	48.00	5904.	4293.	1464.	864.4
1.03	1.00	49	49.00	5558.	4746.	1564.	864.7
1.03	2.00	50	50.00	5254.	4953.	1610.	864.9
1.03	3.00	51	51.00	5039.	5013.	1623.	864.9
1.03	4.00	52	52.00	4964.	5009.	1622.	864.9
1.03	5.00	53	53.00	4944.	4992.	1618.	864.9
1.03	6.00	54	54.00	4956.	4979.	1616.	864.9
1.03	7.00	55	55.00	5087.	4992.	1618.	864.9
1.03	8.00	56	56.00	5253.	5047.	1631.	864.9
1.03	9.00	57	57.00	5396.	5134.	1650.	865.0
1.03	10.00	58	58.00	5516.	5277.	1671.	865.1
1.03	11.00	59	59.00	5670.	5425.	1691.	865.1
1.03	12.00	60	60.00	5794.	5569.	1710.	865.2
1.03	13.00	61	61.00	5885.	5695.	1727.	865.2
1.03	14.00	62	62.00	5945.	5798.	1741.	865.3
1.03	15.00	63	63.00	5976.	5874.	1751.	865.3
1.03	16.00	64	64.00	5983.	5923.	1758.	865.3
1.03	17.00	65	65.00	5967.	5947.	1761.	865.3
1.03	18.00	66	66.00	5930.	5948.	1761.	865.3
1.03	19.00	67	67.00	5876.	5927.	1759.	865.3
1.03	20.00	68	68.00	5807.	5887.	1753.	865.3
1.03	21.00	69	69.00	5723.	5830.	1745.	865.3
1.03	22.00	70	70.00	5627.	5758.	1736.	865.3
1.03	23.00	71	71.00	5522.	5672.	1724.	865.2
1.04	0.00	72	72.00	5407.	5575.	1711.	865.2
1.04	1.00	73	73.00	5286.	5468.	1696.	865.1
1.04	2.00	74	74.00	5159.	5353.	1681.	865.1
1.04	3.00	75	75.00	5023.	5230.	1664.	865.0
1.04	4.00	76	76.00	4883.	5117.	1646.	865.0
				1740	1601	1601	

1.04	7.00	77	77.00	4587.	4909.	1600.	864.8
1.04	5.00	78	78.00	4457.	4787.	1573.	864.8
1.04	7.00	79	79.00	4342.	4666.	1546.	864.7
1.04	8.00	80	80.00	4231.	4547.	1520.	864.6
1.04	9.00	81	81.00	4118.	4430.	1494.	864.5
1.04	10.00	82	82.00	4005.	4314.	1468.	864.4
1.04	11.00	83	83.00	3891.	4199.	1443.	864.3
1.04	12.00	84	84.00	3778.	4084.	1417.	864.3
1.04	13.00	85	85.00	3665.	3970.	1392.	864.2
1.04	14.00	86	86.00	3553.	3856.	1367.	864.1
1.04	15.00	87	87.00	3443.	3743.	1342.	864.0
1.04	16.00	88	88.00	3333.	3673.	1316.	863.9
1.04	17.00	89	89.00	3226.	3627.	1285.	863.9
1.04	18.00	90	90.00	3120.	3575.	1250.	863.7
1.04	19.00	91	91.00	3038.	3517.	1211.	863.6
1.04	20.00	92	92.00	2968.	3460.	1171.	863.5
1.04	21.00	93	93.00	2898.	3449.	1128.	863.4
1.04	22.00	94	94.00	2830.	3437.	1080.	863.2
1.04	23.00	95	95.00	2762.	3424.	1027.	863.0
1.05	0.00	96	96.00	2694.	3409.	971.	862.9
1.05	1.00	97	97.00	2628.	3299.	913.	862.7
1.05	2.00	98	98.00	2562.	3067.	865.	862.5
1.05	3.00	99	99.00	2498.	2890.	828.	862.4
1.05	4.00	100	100.00	2434.	2750.	798.	862.3
1.05	5.00	101	101.00	2372.	2636.	774.	862.2
1.05	6.00	102	102.00	2310.	2538.	754.	862.2
1.05	7.00	103	103.00	2250.	2453.	736.	862.1
1.05	8.00	104	104.00	2191.	2377.	720.	862.1
1.05	9.00	105	105.00	2133.	2306.	706.	862.0
1.05	10.00	106	106.00	2077.	2240.	692.	862.0
1.05	11.00	107	107.00	2021.	2176.	679.	861.9
1.05	12.00	108	108.00	1967.	2116.	666.	861.9
1.05	13.00	109	109.00	1913.	2058.	654.	861.9
1.05	14.00	110	110.00	1861.	2001.	642.	861.8
1.05	15.00	111	111.00	1810.	1946.	631.	861.8
1.05	16.00	112	112.00	1761.	1893.	620.	861.7
1.05	17.00	113	113.00	1716.	1848.	609.	861.7
1.05	18.00	114	114.00	1677.	1804.	598.	861.7
1.05	19.00	115	115.00	1637.	1761.	588.	861.6
1.05	20.00	116	116.00	1597.	1719.	577.	861.6
1.05	21.00	117	117.00	1558.	1678.	567.	861.6
1.05	22.00	118	118.00	1520.	1638.	558.	861.6
1.05	23.00	119	119.00	1483.	1598.	548.	861.5
1.06	0.00	120	120.00	1447.	1559.	539.	861.5
1.06	1.00	121	121.00	1411.	1521.	529.	861.5
1.06	2.00	122	122.00	1377.	1484.	520.	861.4
1.06	3.00	123	123.00	1343.	1448.	512.	861.4
1.06	4.00	124	124.00	1310.	1413.	503.	861.4
1.06	5.00	125	125.00	1278.	1378.	495.	861.3
1.06	6.00	126	126.00	1247.	1344.	487.	861.3
1.06	7.00	127	127.00	1217.	1311.	479.	861.3

17

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
HYDROGRAPH AT	(159.70) (158.56) (144.51) (96.45) (65.79)		
2	5580. 4978. 2530. 912. 4.90		
	(158.01) (140.97) (71.63) (25.82) (12.69)		
2-COMBINED			
2	6140. 5947. 5603. 4137. 30.30		
	(173.86) (168.40) (158.66) (117.14) (78.48)		
ROUTED TO			
3	5948. 5914. 5518. 4099. 30.30		
	(168.42) (167.47) (156.25) (116.07) (78.48)		

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PMP	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF FAILURE HOURS
1		923.30	923.30	927.70	0.00	929.34	15245.	5640.	37.00	65.00
		0.	0.	11050.						0.00
		0.	0.	3073.						
		SUMMARY OF DAM SAFETY ANALYSIS								

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM	RATIO OF PMP	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF FAILURE HOURS
1		859.75	859.75	863.50	0.00	865.34	1761.	5948.	46.00	65.00
		0.	0.	1172.						0.00
		0.	0.	3460.						
		SUMMARY OF DAM SAFETY ANALYSIS								

1 *****
 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 25 SEP 78

MUSOUT2 07:53 FEB 06, '79

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 25 SEP 78

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

- 1 RUNOFF HYDROGRAPH AT
- 2 ROUTE HYDROGRAPH TO
- 2 RUNOFF HYDROGRAPH AT
- 2 COMBINE 2 HYDROGRAPHS AT
- 3 ROUTE HYDROGRAPH TO
- END OF NETWORK

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 25 SEP 78

RUN DATE# 79/02/06.
TIME# 07.48.21.

LAKE MUSCONETCONG DAM
9 PMF
N.J. DAM INSPECTION

NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
150	1	0	0	0	0	0	0	4	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 8 LRTIO= 1

RTIOS= 1.00 .90 .80 .70 .60 .50 .40 .30

SUB-AREA RUNOFF COMPUTATION

20

ROUTING DATA

QLOSS	CLOSS	AVG	IPRES	ISAME	IOPT	IPMP	LSTR	
0.0	0.000	0.00	1	0	0	0	0	
	NSTPS	NSTDLD	LAG	AMSKK	X	TSK	STORA	ISPRAT
	1	0	0	0.000	0.000	0.000	0.	-1
STAGE	923.30	924.30	925.30	926.30	927.70	928.70	929.70	931.70
FLOW	0.00	333.00	942.00	1730.00	3073.00	4497.00	8355.00	10651.00
SURFACE AREA=	2474.	2491.	2508.	2525.	2542.	2559.	2576.	2593.
	2644.	2661.						2627.
CAPACITY=	0.	2482.	4982.	7498.	10032.	12582.	15150.	17734.
	25590.	28242.					20336.	22954.
ELEVATION=	923.	924.	925.	926.	927.	928.	929.	930.
	933.	934.					931.	932.

CREL	SPWID	COOM	EXPW	ELEVL	COOL	CAREA	EXPL
923.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0

TOPEL	COOD	EXPD	DAMWID
927.7	0.0	0.0	0.

PEAK OUTFLOW IS	5640. AT TIME	65.00 HOURS
PEAK OUTFLOW IS	4804. AT TIME	66.00 HOURS
PEAK OUTFLOW IS	4032. AT TIME	66.00 HOURS
PEAK OUTFLOW IS	3296. AT TIME	67.00 HOURS
PEAK OUTFLOW IS	2679. AT TIME	68.00 HOURS
PEAK OUTFLOW IS	2120. AT TIME	69.00 HOURS
PEAK OUTFLOW IS	1574. AT TIME	70.00 HOURS
PEAK OUTFLOW IS	1079. AT TIME	71.00 HOURS

SUB-AREA RUNOFF COMPUTATION

COMPUTE HYDROGRAPH - MUSCONETCONG LOCAL

ISTAQ 2 ICOMP 0 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 ISTAGE 0 IAUTO 0

IHYDG 1 IUHG 1 TAREA 4.90 TRSDA 4.90 TRSPC .80 RATIO 0.000 ISNOW 0 ISAME 0 LOCAL 0

PRECIP DATA
 SPFE 0.00 PMS 22.40 R6 112.00 R12 123.00 R24 132.00 R48 142.00 R96 0.00

LOSS DATA
 LROPT 0 STRKR 0.00 DLTRR 0.00 RTIOL 1.00 ERAIN 0.00 STRKS 0.00 RTIOK 1.00 STRTL 1.00 CNSTL .15 ALSMX 0.00 RTIMP 0.00

UNIT HYDROGRAPH DATA
 TP= 6.00 CP= .58 NTA= 0

RECESSION DATA
 STRTQ= -2.00 QRCSEN= 0.00 RTIOR= 1.00

UNIT HYDROGRAPH 37 END-OF-PERIOD ORDINATES, LAG= 6.00 HOURS, CP= .58 VOL= 1.00
 19. 70. 140. 276. 309. 308. 274. 233. 198.
 168. 143. 122. 103. 88. 75. 63. 54. 39.
 33. 28. 24. 20. 17. 15. 12. 11. 8.
 6. 5. 4. 3. 2.

MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q MO.DA HR.MN PERIOD RAIN EXCS LOSS COMP Q
 SUM 25.45 20.64 4.81 66438.
 (646.) (524.) (122.) (1881.31)

COMBINE HYDROGRAPHS

COMBINE OUTFLOW OF HOPATCONG WITH LOCAL INFLOW OF MUSCONETCONG

ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO

2 4 0 0 0 0 0 0 0 0

HYDROGRAPH ROUTING

ROUTING COMPUTATIONS - MUSCONETCONG

ISTAQ	3	ICOMP	1	IECON	0	ITAPE	0	JPLT	0	JPRT	0	INAME	1	ISTAGE	0	IAUTO	0
QLOSS	0.0	AVG	0.00	IRES	1	ISAME	0	IOPT	0	IPMP	0	LSTR	0				
NSTPS	1	NSTD	0	LAG	0	AMSKK	X	TSK	0.000	STORA	0.	ISPRAT	-1				
STAGE	859.75	861.75	862.75	863.50	864.00	865.00	866.00	867.00	868.00	869.00							
FLOW	0.00	605.00	1895.00	3400.00	316.	313.	319.	322.	325.	328.	331.	334.					

SURFACE AREA=	307.	310.	313.	316.	319.	322.	325.	328.	331.	334.
CAPACITY=	0.	308.	621.	934.	1252.	1572.	1896.	2222.	2552.	2884.
ELEVATION=	860.	861.	862.	863.	864.	865.	866.	867.	868.	869.

CREL	859.8	SPWID	0.0	COOW	0.0	EXPW	0.0	ELEVL	0.0	COQL	0.0	CAREA	0.0	EXPL	0.0
------	-------	-------	-----	------	-----	------	-----	-------	-----	------	-----	-------	-----	------	-----

TOPEL	863.5	COQD	0.0	EXPD	0.0	DAMWID	0.
-------	-------	------	-----	------	-----	--------	----

PEAK OUTFLOW IS 5948. AT TIME 65.00 HOURS

PEAK OUTFLOW IS 5020. AT TIME 66.00 HOURS

PEAK OUTFLOW IS 4215. AT TIME 67.00 HOURS

PEAK OUTFLOW IS 3422. AT TIME 50.00 HOURS

PEAK OUTFLOW IS JUBB. AT TIME 49.00 HOURS
 PEAK OUTFLOW IS 2527. AT TIME 49.00 HOURS
 PEAK OUTFLOW IS 1970. AT TIME 49.00 HOURS
 PEAK OUTFLOW IS 1445. AT TIME 49.00 HOURS

***** ***** ***** *****

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS							
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8
				1.00	.90	.80	.70	.60	.50	.40	.30
HYDROGRAPH AT	1	25.40 (65.79)	1	15026. (425.48)	13523. (382.93)	12020. (340.38)	10518. (297.83)	9015. (255.29)	7513. (212.74)	6010. (170.19)	4508. (127.64)
ROUTED TO	2	25.40 (65.79)	1	5640. (159.70)	4804. (136.04)	4032. (114.18)	3296. (93.32)	2679. (75.85)	2120. (60.02)	1574. (44.57)	1079. (30.55)
HYDROGRAPH AT	2	4.90 (12.69)	1	5580. (158.01)	5022. (142.20)	4464. (126.40)	3906. (110.60)	3348. (94.80)	2790. (79.00)	2232. (63.20)	1674. (47.40)
2 COMBINED	2	30.30 (78.48)	1	6140. (173.86)	5499. (155.72)	4859. (137.58)	4217. (119.42)	3605. (102.07)	3004. (85.07)	2403. (68.06)	1803. (51.04)
ROUTED TO	3	30.30 (78.48)	1	5948. (168.42)	5020. (142.16)	4215. (119.36)	3422. (96.90)	3086. (87.40)	2527. (71.57)	1970. (55.79)	1445. (40.92)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
		923.30	923.30	927.70
		0.	0.	11050.
		0.	0.	3073.

24

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	929.34	1.64	15245.	5640.	37.00	65.00	0.00
.90	928.87	1.17	14047.	4804.	32.00	66.00	0.00
.80	928.37	.67	12771.	4032.	25.00	66.00	0.00
.70	927.86	.16	11449.	3296.	13.00	67.00	0.00
.60	927.29	0.00	10004.	2679.	0.00	68.00	0.00
.50	926.71	0.00	8525.	2120.	0.00	69.00	0.00
.40	926.10	0.00	6999.	1574.	0.00	70.00	0.00
.30	925.47	0.00	5418.	1079.	0.00	71.00	0.00

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
0.	859.75	859.75	863.50
0.	0.	0.	1172.
0.	0.	0.	3460.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	865.34	1.84	1761.	5948.	46.00	65.00	0.00
.90	864.91	1.41	1625.	5020.	42.00	66.00	0.00
.80	864.36	.86	1446.	4215.	36.00	67.00	0.00
.70	863.03	0.00	1022.	3422.	0.00	50.00	0.00
.60	862.54	0.00	869.	3086.	0.00	49.00	0.00
.50	862.17	0.00	752.	2527.	0.00	49.00	0.00
.40	861.80	0.00	636.	1970.	0.00	49.00	0.00
.30	861.40	0.00	511.	1445.	0.00	49.00	0.00

1*****
 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 25 SEP 78

APPENDIX 5

REFERENCES

LAKE MUSCONETCONG DAM

APPENDIX 5

REFERENCES

LAKE MUSCONETCONG DAM

1. Memorandum to President & Board of Directors, Morris Canal & Banking Co., from C.C. Vermeule, dated 13 July 1925.
2. Report titled "Improvement of Lake Musconetcong," by C.C. Vermuele, Morris Canal & Banking Co., dated 20 Dec. 1930.
3. Memorandum to Mr. A.L. Sherman, State Water Policy Commission, from H.T. Critchlow, dated 21 May 1931.
4. Letter to Mr. H.T. Critchlow from C.C. Vermeule, dated 29 May 1931.
5. Letter to Mr. A.L. Sherman, from C.C. Vermeule, dated 29 May 1931.
6. Memorandum to Mr. C.C. Vermeule from H.T. Critchlow, dated 2 June 1931.
7. Letter to Mr. H.T. Critchlow from C.C. Vermeule, dated 4 June 1931.
8. Memorandum to Mr. A.L. Sherman from H.T. Critchlow, dated 6 June 1931.
9. Letter to Mr. C.C. Vermeule from H.T. Critchlow, dated 9 June 1931.
10. Letter to Mr. H.T. Critchlow from C.C. Vermeale, dated 11 June 1931.
11. Report on Dam Application #186, by J.N. Brooks and H.T. Critchlow, dated 3 July 1931.
12. Acknowledgement of Application for Permit for Construction or Repair of Dam, to Dr. H.B. Kummel, Morris Canal & Banking Company, dated 21 July 1931.
13. Permit to Morris Canal & Banking Company by State Water Policy Commission, dated 29 July 1931.
14. Inspection Report by G.R. Shanklin, dated 8 Aug. 1932.
15. Annual Report by M. Berkowitz, dated 5 June 1968.

16. Chow, Ven Te, Ph.D, Open Channel Hydraulics, McGraw-Hill Book Company, 1959.
17. United States Dept. of Agriculture, Soil Conservation Service SCS National Engineering Handbook Section 4 Hydrology NEH-Notice 4-102, August 1972.
18. United States Dept. of Agriculture, Soil Conservation Service, Somerset, N.J. Urban Hydrology for Small Watersheds, Technical Release No. 55, January 1975.
19. United States Dept. of Commerce Weather Bureau, April 1956 Hydrometeorological Report No. 33, Washington, D.C.
20. United States Dept. of Interior, Bureau of Reclamation Design of Small Dams, Second Edition 1973, Revised Print 1977.
21. Wolfe, P.E., 1977, The Geology and Landscapes of New Jersey, Crane, Russak & Company, Inc., New York, New York, 351 pp.

Drawings

1. Dwg No 150, General Plan of Dam Section Thru Culvert, by Morris Canal & Banking Co., dated 1 July 1, 1925.
2. Dwg No 151, Elevations Sections Gatehouse, by Morris Canal & Banking Co., dated 1 July 1925.
3. Dwg No 152, Concrete & Steel Details, by Morris Canal & Banking Co., dated 1 July 1925.
4. Plan of Reinf. of Cap of Present Spillway, By C.C. Vermeule, approved by State Water Policy Commission July 1931.
5. Longitudinal Sections with Elevation of Spillway, by C.C. Vermeule, approved by State Water Policy Commission July 1931.